GREAT ISLAND ENTRY DRIVEWAY IMPROVEMENTS

DARIEN, CONNECTICUT

JULY 2, 2024

PREPARED FOR

PREPARED BY

TOWN OF DARIEN

2 RENSHAW ROAD

DARIEN, CT 06820

(203) 656-7300

REDNISS & MEAD, INC.

22 FIRST STREET

STAMFORD, CT 06905

(203) 327-0500

DESTEFANO & CHAMBERLAIN, INC. 50 THORPE STREET

50 THORPE STREET FAIRFIELD, CT 06824 (203) 254-7131

SHEET INDEX

SHEET No. SHEET TITLE
CV-1 COVER SHEET
SE-1 ROADWAY PLAN & PROFILE
SE-2 GRADING PLAN
SE-3 UTILITY PLAN
SE-4 SEDIMENT & EROSION CONTROL PLAN
SE-5 DETAILS (1 OF 3)
SE-6 DETAILS (2 OF 3)
SE-7 DETAILS (3 OF 3)
LP.1 LANDSCAPE PLAN
LP.2 LANDSCAPE DETAILS
RW-1 RETAINING WALL DESIGN
RW-2 RETAINING WALL DESIGN





LOCATION MAP SCALE: 1"=400'


JON ZAGRODZKY, FIRST SELECTMAN


EDWARD L. GENTILE JR., P.E., DIRECTOR OF PUBLIC WORKS















24" GALLERY DETAIL



INFILTRATION SYSTEM NOTES

- 1. ALL GALLERIES TO HANDLE H-20 LOADINGS AND SHALL COMPLY WITH THE DETAIL. INTERIOR SECTIONS TO HAVE NO END WALLS. END SECTIONS TO HAVE ONE END
- WALL AND ACCESS COVER. . ALL GALLERY SECTIONS TO HAVE HOLES BROKEN TO ALLOW FLOW PRIOR TO
- PLACEMENT.
- 3. THERE SHALL BE A MINIMUM 6" LAYER OF No. 4 CRUSHED STONE BELOW ALL GALLERIES. 4. THERE SHALL BE A MINIMUM OF 12" OF 11/4" CRUSHED STONE ON THE SIDES & ENDS OF
- THE OUTER GALLERIES. . GEOTEXTILE TO BE "MIRAFI HP 360" OR APPROVED EQUIVALENT. ELIMINATE WRINKLES
- IN THE GEOTEXTILE AND ENSURE NOT TO DAMAGE IT DURING CONSTRUCTION. . THE INFILTRATION SYSTEM IS TO REMAIN DISCONNECTED UNTIL UP GRADIENT AREAS ARE FULLY STABILIZED. THE INFILTRATION SYSTEMS SHALL BE MINIMUM OF 12" ABOVE HIGH GROUNDWATER

MANUFACTURED BY CAMPBELL FOUNDRY COMPANY, HARRISON, NJ. RAISE CASTING

- AND SHALL BE MINIMUM OF 10' FROM ANY FOOTING DRAIN. 8. A 6" BY 5' BY 4' CONCRETE SLAB (1-2-3 CONCRETE) SHALL BE INSTALLED AT ANY PIPE ENTRANCE TO THE GALLERIES TO PREVENT EROSION. 9 FACH GALLERY RUN TO HAVE ACCESS MHS AS SHOWN ON THE PLAN. CASTING AND COVER SHALL BE FOUAL TO PATTERN NO. 1202B (WITH THE WORD "DARIEN" ON IT) AS
- TO GRADE USING SOLID CONCRETE BLOCK AND MORTAR. 10 REMOVE ANY TOPSOIL PRIOR TO INSTALLATION OF GALLERY
- 11. CONTACT THE DESIGN ENGINEER THREE DAYS PRIOR TO EXCAVATION FOR THE GALLERIES. DURING THE EXCAVATION, THE DESIGN ENGINEER MAY REVISE THE ELEVATIONS OF THE GALLERIES IF FIELD CONDITIONS DICTATE.
- 12. ALL CRUSHED STONE SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818, ARTICLE M.01.01. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS, OR DISINTEGRATED PIECES, MUD, DIRT, OR OTHER DELETERIOUS MATERIAL.
- 13. MAINTENANCE OF ALL ONSITE DRAINAGE FACILITIES SHALL BE THE RESPONSIBILITY OF THE TOWN OF DARIEN, UPON COMPLETION OF PROJECT, CONTRACTOR TO CLEAN ALL DRAINAGE FACILITIES PRIOR TO FINAL PAYMENT AND RETAINAGE RELEASE.

12" STANDPIPE 12" PVCP · INSTALL 90° PVC ELBOW OR BELL TRAP -12" PVCP TO/FROM INF#1 ON OUTLET PIPE INV.IN=6.40 SUMP

- CAMPBELL FOUNDRY PATTERN #3408

- 1. ALL JUNCTION BOX COMPONENTS TO BE PRE-CAST REINFORCED CONCRETE, ABLE TO WITHSTAND THE APPLIED EARTH LOADS WITH AN H-20 TRUCK LOAD.
- 2. ALL JOINTS TO BE MORTARED.
- 3. JUNCTION BOX SHALL CONFORM TO ASTM C478.
- 4. ALL CRUSHED STONE SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818. ARTICLE M.01.01. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS OR DISINTEGRATED PIECES, MUD, DIRT OR OTHER DELETERIOUS MATERIAL.

FLAT TOP CATCH BASIN W/ STANDPIPE (CB#3)

N.T.S.

CAMPBELL FOUNDRY PATTERN #2548-1942 (4" CURB TYPF) OR #3408 (FLAT TOP, CB#3) **PRECAST** TOP SLAB **PRECAST** RISER SECTION CAMPBELL FOUNDRY BELL TRAP OR "SNOUT" - MORTAR FILLED JOINT -- PRECAST SUMP 24" MIN. PLACE CATCH BASIN ON 6" LAYER OF CRUSHED STONE NOTES:

- 1. ALL CATCH BASIN COMPONENTS TO BE PRE-CAST REINFORCED CONCRETE, ABLE TO WITHSTAND THE APPLIED EARTH LOADS WITH AN H-20 TRUCK LOAD.
- ALL JOINTS TO BE MORTARED. 3. CATCH BASIN SHALL CONFORM TO ASTM C478.
- 4. ALL CRUSHED STONE SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818, ARTICLE M.01.02. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS OR DISINTEGRATED PIECES, MUD, DIRT OR OTHER DELETERIOUS MATERIAL.
- 5. IF CRUSHED STONE IS TO BE PLACED ON FILL. ALL FILL BELOW THE CB SHALL BE COMPACTED TO 95% OF THE MAXIMUM PRT DENSITY AS PER ASTM D.1557.

TEST PIT RESULTS

Subsurface Soil Investigation Recorded By: JTF Soil Profile Hole: PH#1 Test Pit #: 1 Date: 11/09/2023 Depth: 26" Sanitarian: N/A 9:28 AM Inspector: JTF Ledge at: 69" Mottling at: N/A Minimum Uniform Drop: 6/16 inches in 10 minutes Water at: N/A Roots at: Percolation Rate = 1"drop in 26.67 minutes Depth: 69' Soil Description 0"-18" 18"-44" Orange-Brown Silty Loam 11:30 AM 44"-69" Grey Fine Sandy Loam. Ledge @ 69" 11:40 AM 11:50 AM Subsurface Soil Investigation 12:00 PM 12:10 PM Test Pit #: 2 Date: 11/09/2023 12:20 PM Inspector: JT Sanitarian: N/A 12:30 PM Ledge at: N/A Mottling at: N/A Recorded By: JTF Hole: PH#2 Water at: N/A Roots at: Depth: 28" Depth: 86' Soil Description 9:30 AM 0"-18" Topsoil/Fill 18"-52" Orange-Brown Silty Loam Minimum Uniform Drop: 13/16 inches in 10 minutes 52"-86" Grey Fine Sandy Loam Percolation Rate = 1"drop in 12.31 minutes Subsurface Soil Investigation Soil Profile Test Pit #: 3 Date: 11/09/2023 11:30 AM Inspector: JTF Sanitarian: N/A 11:40 AM 11:50 AM 12:00 PM

Nater at: N/A		Roots at:
Depth: 74"	Soil Description	
0''-4"	Topsoil	
4"-43"	Brown Silty Loam	
43"-74"	Orange-Brown Silty Loam	

	Subsurface Soil Hivesti	gation	
	Soil Profile	Soil Profile	
Test Pit #: 4		Date: 11/09/2023	
Inspector: JTF		Sanitarian: N/A	
Ledge at: N/A		Mottling at: N/A	
Water at: N/A		Roots at:	
Depth: 84"	Soil Description		
0''-12"	Topsoil		
12"-84"	Orange-Brown Sandy Loam		

FILTER FABRIC -(Mirafi 140N or equ.)

12" PERFORATED

CRUSHED-STONE

SUITABLE ~ BASE

- PRECAST CONCRETE BOX JB#1: NO BELL TRAP OR ELBOW. FORM INVERT IN BOTTOM OF STRUCTURE MORTAR FILLED KNOCKOUTS AS JOINT (TYP) NECESSARY (TYP) CRUSHED

1. ALL COMPONENTS TO BE PRE-CAST REINFORCED CONCRETE, ABLE TO WITHSTAND THE APPLIED EARTH LOADS OF AN H-20 TRUCK LOAD.

PERCOLATION TEST

RESULTS

Recorded By: JTF

11:34 AM

11:44 AM

11:54 AM

12:04 PM

12:14 PM

12:24 PM

12:34 PM

Recorded By: JTF

11:35 AM

11:45 AM

11:55 AM

12:05 PM

12:15 PM

12:25 PM

12:35 PM

Hole: PH#4

Depth: 24"

9:35 AM

Hole: PH#3

Depth: 19"

9:34 AM

Date: 11/09/23

Project: 8004

Diameter: 8"

1/16

9/16

6/16

6/16

6/16

Date: 11/09/23

Inches

1 12/16

12/16

10/16

10/16

10/16

Project: 8004

Diameter: 8"

2:00 hrs

Reading In Inches Increment Drop In

2:00 hrs

Reading In Inches Increment Drop In

Minimum Uniform Drop: 6/16 inches in 10 minutes

7 13/16

8 14/16

9 7/16

9 14/16

10 4/16

10 10/16

Minimum Uniform Drop: 10/16 inches in 10 minutes

Total

14 12/16

15 12/16

16 8/16

17 2/16

17 12/16

18 6/16

BRICK AND MORTAR

Percolation Rate = 1"drop in 16.00 minutes

Percolation Rate = 1"drop in 26.67 minutes

Date: 11/09/23

Project: 8004

12/16

8/16

8/16

6/16

2 7/16

1 8/16

1 5/16

13/16

13/16

13/16

Date: 11/09/23

Project: 8004

Diameter: 8"

2:00 hrs

Reading In Inches Increment Drop In

6/16

Diameter: 8"

2:02 hrs

Reading In Inches Increment Drop In

17 7/16

17 15/16

18 7/16

18 13/16

19 3/16

17 1/16

18 9/16

19 14/16

20 11/16

21 8/16

22 5/16

12:10 PM

12:20 PM

12:30 PM

CAMPBELL FOUNDRY

PATTERN #2802 -


(SOLID COVER)

- 2. ALL JOINTS TO BE MORTARED.
- 3. JUNCTION BOXES SHALL CONFORM TO ASTM C478.
- 4. CRUSHED STONE BENEATH JUNCTION BOX SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818, ARTICLE M.01.01. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS OR DISINTEGRATED PIECES, MUD, DIRT OR OTHER DELETERIOUS MATERIAL.


JUNCTION BOX

ADD ALT#3


CATCH BASIN DETAIL



INVERT TO BE CONSTRUCTED OF CLASS 'C' CONCRETE (CT. DOT FORM 818). BENCH WALLS & FLOW CHANNELS SHALL BE CONSTRUCTED OF SOLID CONCRETE FLOW CHANNELS TO MATCH THE INVERTS AND SIZE OF THE PIPES, AND SHALL BE CONSTRUCTED SUCH THAT A SMOOTH UNINTERRUPTED FLOW IS ASSURED.



MANHOLE INVERT N.T.S.



- 1. ALL JUNCTION BOX COMPONENTS TO BE PRE-CAST REINFORCED CONCRETE, ABLE TO WITHSTAND THE APPLIED EARTH LOADS WITH AN H-20 TRUCK LOAD.
- . ALL JOINTS TO BE MORTARED. 3. JUNCTION BOX SHALL CONFORM TO ASTM C478.
- 4. ALL CRUSHED STONE SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818, ARTICLE M.01.01. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS OR DISINTEGRATED PIECES, MUD, DIRT OR OTHER DELETERIOUS MATERIAL.

CURB TYPE CATCH BASIN W/ STANDPIPE (CB#6) N.T.S.

WATER STOP: 10' UPSTREAM OF STRUCTURES AND WHERE SHOWN (OR AS DIRECTED BY INSPECTING ENGINEER), FOUNDATION MATERIAL, BEDDING, HAUNCHING, INITIAL BACKFILL, AND THE BOTTOM FOOT OF GENERAL BACKFILL TO BE REPLACED WITH SM, SC, OR ML SOIL AS PER UNIFIED SOIL CLASSIFICATION SYSTEM" WITH MAXIMUM PARTICLE SIZE OF 1-1/2", FOR 3 LINEAR FEET OF TRENCH. WATER STOP TO BE KEYED INTO TRENCH BOTTOM AND WALLS A MINIMUM OF ONE FOOT. NO STONES LARGER THAN SHALL BE WITHIN 12" OF THE PIPE.

INV.=14.5

ADD ALT#3

4" MIN. IN EARTH EXCAVATION 12" MIN. IN ROCK EXCAVATION.

ALL FOUNDATION, INITIAL BACKFILL & BACKFILL MATERIAL TO BE APPROVED BY THE INSPECTING ENGINEER.

ANY DEVIATION FROM THESE METHODS & MATERIALS MUST BE APPROVED IN WRITING BY THE INSPECTING ENGINEER. ALL MATERIAL TO BE COMPACTED TO 95% OF THE MAX. DRY DENSITY AS DETERMINED BY ASTM D1557, EXCEPT COMPACTED BACKFILL" NOT UNDER PAVEMENT WHICH SHALL BE COMPACTED

TO A DENSITY AT LEAST EQUAL TO THAT OF THE ADJACENT UNDISTURBED MATERIAL.

AFTER PIPE IS INSTALLED,

MATERIAL TO 1/4 BC.

BACKFILL TRENCH WITH BEDDING

1. CRUSHED STONE SHALL BE GRADATION

NO. 4 PER CONN. DOT, FORM 818,

2. 12" PVCP PIPE SHALL HAVE PERFORATIONS


CRUSHED STONE

LEVEL SPREADER

N.T.S.

ON THE SIDES & BOTTOM OF THE PIPE.


COMPACTED BACKFILL SHALL BE WELL GRADED MATERIAL FREE OF ORGANICS, FROZEN MATERIAL & PARTICLES LARGER BACKFILL MUST BE PLACED & COMPACTED IN SIX INCH (6") LAYERS



PVC/RCP PIPE TRENCH BEDDING DETAIL (48" DIA. & UNDER) N.T.S.

12/26/2023	ISSUED FOR EPC & P&Z
01/30/2021	1 ZC RESOBI 11551OT4
01/30/2024	PZC RESUBMISSION
02/27/2024	ISSUED FOR CONSTRUCTION
07/02/2024	REVISED RETAINING WALLS
	02/27/2024

DETAILS (2 OF 3) DEPICTING GREAT ISLAND ENTRY DRIVE DARIEN, CT PREPARED FOR **TOWN OF DARIEN**




PERMITTING

www.rednissmead.com

LAND SURVEYING CIVIL ENGINEERING Planning & Zoning Consulting

This document and copies thereof are valid only if they bear the ignature and embossed seal of the designated licensed professio nauthorized alterations render any declaration hereon null & vo 22 First Street | Stamford, CT 06905 Tel: 203.327.0500 | Fax: 203.357.1118

N.T.S.



CAMPBELL FOUNDRY PATTERN

PRECAST REINFORCED CONCRETE

ELONGATED, LAMINATED, FRIABLE, MICACEOUS

OR DISINTEGRATED PIECES, MUD. DIRT OR

OTHER DELETERIOUS MATERIAL

#1202B. COVER SHALL HAVE

THE WORD "DARIEN" ON IT.

STORM MANHOLE DETAIL

CASTING TO CONFORM

AND CASTING

REFER TO MANHOLE INVERT DETAIL


1:2:3.5 MIX CONCRETE FOR BASE,


PRECAST BASE CAN BE USED


ADJUST TO GRADE WITH COURSES


OF BRICK MORTARED TO MANHOLE

WITH ASTM A-48









CAST-IN-PLACE CONCRETE Concrete strength at 28 days: 4,000 psi.

DO NOT ALLOW RELEASE AGENT TO COME IN CONTACT WITH REINFORCING STEEL OR HARDENED CONCRETE

Calcium chloride shall not be used.

Air-entrain all concrete exposed to the weather, omit air-entrainment from interior slabs with trowel finish.

Reinforcing steel: ASTM A615 grade 60.

Concrete work shall be in accordance with ACI 301-16 and ACI 318-11.

Maximum slump: 5 inches.

Limit length of concrete wall pours to 50 ft at any one time. Interrupt horizontal reinforcing steel at all joints. Provide keyed expansion joint with compressible filler as shown on RW-2.

Provide 4" PVC weep hole thru concrete wall spaced 4'-0" o.c.

All embedded masonry anchors, such as dovetail slots, shall be hot dip galvanized. Minimum 12 ga. steel thickness unless


A testing laboratory shall cast 4 test cylinders for each 50 yards for each day's pour. Slump, air content, and temperature tests shall be performed when cylinders are cast. Test 1 cylinder at 7 days and 2 cylinders at 28 days. Hold 4th cylinder for 56 day break if needed.

Submit concrete mix design for approval

Special Inspections shall be made of reinforcing steel and concrete placement.

Cold weather concrete work shall conform to ACI 306.1. Protect concrete from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures. Use non-chloride accelerating admixture in all concrete that will be placed in temperatures below 40° F for 24 hours following pour.

CONCRETE MIN. COVER <u>Conditions</u>



Description

GREAT ISLAND ENTRY DRIVE

DeStefano &

Chamberlain

Incorporated

Structural and Architectural Engineering

50 Thorpe Street, Fairfield, CT 06824-5725 C 203 254-7131 www.dcstructural.com

professional service are and shall remain the property of

DeStefano & Chamberlain. Documents are not to be used, in whole or in part, for other projects or purposes or by any other parties than those authorized by

contract without the specific written authorization of

Copyright 2024 DeStefano & Chamberlain, Inc.

Drawings and Specifications, as instruments of

Ownership and conditions of use:

DeStefano & Chamberlain.

Revisions/Submission:

Date

RETAINING WALL PLAN & 3D

DARIEN. CT

Project Number:	Date:	
24-2174	6-26-2024	
Scale: As indicated	Drawing number:	
Designed by: KHC		
Drawn by: DC	RW-1	
Checked by: DC		

Note: the 3D views below only depict the cast-in-place concrete work. There is also stone masonry veneer and parapet, which are not shown in these 3D views.

Inspections shall be made prior to tamping the soil or setting footing forms. The Inspector shall verify that soil is suitable

The Contractor shall be responsible for all dewatering, shoring, sheeting, or bracing required to maintain a safe, dry, and

Where suitable bearing soils is not encountered at indicated bottom of footing elevation carry excavations deeper as

The Contractor shall verify the location of all underground utility lines, sewers, and fuel storage tanks to avoid any

Backfill shall be compacted granular soil with not more than 10% passing the #200 sieve, and free of debris and organic

material. If on-site soil does not meet this specification, the Contractor shall bring in soil from off-site at his own expense.

Where bottom of excavation is below the groundwater elevation, place 6 inches of crushed stone above apprpoved

Footing sub-grade shall be compacted using a vibratory tamper or a jumping soil rammer after the soil has been

for the support of foundations and is consistent with the soil identified in the Soil Boring Logs.

damage. Contractor shall contact "Call Before You Dig" prior to any excavation. Dial 811.

subgrade. Crushed stone shall be placed after the subsoil has been inspected, and approved.

Soil adjacent to and below footings shall be kept from freezing at all times.

Exterior footings bearing on soil shall be at least 42" below finished grade.

inspected and approved.


directed by the Engineer.

No footings shall be placed in water.

stable excavation.



BASIS OF DESIGN - STONE VENEER



WALL #3

REFER TO "BASIS OF DESIGN - STONE VENEER" IMAGE ON THIS SHEET FOR

Mortar shall consist of one part Portland Cement, 2 to 3 parts clean sand, not more than 1/4

All necessary dressing or shaping of stone shall be done before the stone is laid in the wall.

Stones at angles or at ends of walls shall be roughly squared and dressed to the required

Stone shall not be laid when the air temperature is below 40 degrees F.

Each stone shall be cleaned and thoroughly saturated with water before being set.

Stones shall not be dropped or slid over the wall but shall be carefully set without jarring

All stones shall be bedded in freshly made mortar. The mortar joints shall be full and the

Joints and beds shall of a thickness to produce a "dry look" with near tight joints at the

The vertical joints in each course shall break joints with those in adjoining courses at least 6

Wherever possible, the face joints shall be pointed before the mortar becomes set. Joints not

Upon completion of the wall, all mortar shall be removed from the face of the stones and the

All ties and anchors shall be hot dip galvanized. Minimum 12 ga. steel thickness unless noted.

In case any stone is moved or the joint broken, the stone shall be taken up, the mortar

pointed at the time the stones are laid shall be thoroughly wet with water and filled with

mortar. The mortar shall be well driven into the joints and finished with a pointing tool.

thoroughly cleaned from the bed and joints, and the stone reset in fresh mortar.

Collar joint between veneer stones and backup wall shall be filled solid with mortar.

The masonry shall be laid to line in courses, roughly leveled up.

stones carefully settled in place before the mortar has set.

wall shall be washed down with a solution of muriatic acid.

WALL #2

No spalls shall be permitted in the beds.

No dressing or hammering which will loosen the stone will be permitted atter it is placed.


INTENDED STYLE OF STONE MASONRY.

part hydrated lime.

stone already laid.

surface of the wall.

6/26/2024 3:54:39 PM



DeStefano &

professional service are and shall remain the property of used, in whole or in part, for other projects or purposes

GREAT ISLAND ENTRY

RW-2