
MASSACHUSETTS DIVISION OF FISHERIES AND WILDLIFE SCHOOLHOUSE POND DAM REMOVAL PROJECT SUTTON, MASSACHUSETTS


OCTOBER 2024

LICT OF DRAWINGS		
LIST OF DRAWINGS		
SHEET NO.	DRAWING NO.	DRAWING TITLE
		GENERAL
1	G-001	COVER SHEET
2	G-002	GENERAL NOTES, ABBREVIATIONS, AND LEGEND
CIVIL		
3	C-101	EXISTING CONDITIONS PLAN
4	C-102	DEMOLITION, EROSION, SEDIMENT, AND WATER CONTROL PLAN
5	C-103	PROPOSED CONDITIONS PLAN
6	C-104	SCHOOLHOUSE CHANNEL CONTROL PLAN 1 OF 3
7	C-105	SCHOOLHOUSE CHANNEL CONTROL PLAN 2 OF 3
8	C-106	SCHOOLHOUSE CHANNEL CONTROL PLAN 3 OF 3
9	C-201	CULVERT PLAN AND DETAILS
10	C-202	MISCELLANEOUS DETAILS
11	C-203	EROSION, SEDIMENT, AND WATER CONTROL DETAILS
12	C-204	BOULDER RIFFLE DETAILS
13	C-205	TRAFFIC MANAGEMENT PLAN
14	C-206	TEMPORARY TURBIDITY CURTAIN
15	C-207	HIGHWAY GUARDRAIL DETAILS (SHEET 1 OF 2)
16	C-208	HIGHWAY GUARDRAIL DETAILS (SHEET 2 0F 2)
17	C-209	GUARDRAIL APPROACH GEOMETRY



PREPARED BY:

Tighe&Bond



DANIEL R. BUTTRICK, PE

DANIEL R. HAMMERBERG, PE

PREPARED FOR:

MASSACHUSETTS DIVISION OF FISHERIES & WILDLIFE

CALEB SLATER, PhD, CHIEF OF HATCHERIES

COMPLETE SET 17 SHEETS

EROSION AND SEDIMENTATION CONTROL NOTES:

- TEMPORARY SEDIMENT AND EROSION CONTROL BY THE CONTRACTOR SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATIONS LISTED BELOW
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING ALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES NECESSARY TO EXECUTE AND COMPLETE THE WORK OF THE CONTRACT, IN COMPLIANCE WITH THE TERMS AND CONDITIONS CONTAINED IN THE CONTRACT AND PROJECT PERMITS. CONTROLS SHOWN ON THE CONTRACT DRAWINGS AND MENTIONED IN THE TECHNICAL SPECIFICATIONS SHALL BE CONSIDERED MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL EMPLOY WHATEVER SUPPLEMENTARY MEASURES NECESSARY TO PROTECT WETLANDS, WATERS, AND ADJACENT AREAS FROM DISTURBANCE OR DISCHARGE OF SEDIMENTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SEDIMENT AND EROSION CONTROLS TO MEET THE CONDITIONS OF ALL APPLICABLE PERMITS AND REGULATIONS. SUCH CONTROLS SHALL BE INSTALLED WHEREVER THE POTENTIAL EXISTS FOR THE DISTURBANCE OF LAND OR THE TRANSPORT OF SEDIMENT.
- EROSION AND SEDIMENTATION CONTROLS SHALL CONSIST OF COMPOST FILTER TUBES INSTALLED PER DETAILS PROVIDED ON SHEET C-203.
- COMPOST FILTER TUBES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF CLEARING AND GRUBBING ACTIVITIES. LOCATION OF COMPOST FILTER TUBES TO BE ADJUSTED UPON COMPLETION OF CLEARING AND GRUBBING BUT PRIOR TO COMMENCEMENT OF GRADING ACTIVITIES
- ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE MAINTAINED IN GOOD CONDITION AND PROPER WORKING ORDER. NECESSARY REPAIRS SHALL BE MADE IMMEDIATELY
- ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE PROPERLY DISPOSED OFF-SITE UPON COMPLETION OF WORK, SITE STABILIZATION AND/OR AUTHORIZATION FROM THE OWNER.
- MAINTAIN AN ADDITIONAL SUPPLY OF EROSION CONTROL MEASURES ONSITE THROUGHOUT THE CONSTRUCTION PERIOD.
- SILT TRAPPED AT BARRIERS SHALL BE REMOVED AND DISPOSED OF IN UPLAND AREAS OUTSIDE BUFFER ZONES. MATERIALS DEPOSITED IN ANY TEMPORARY SETTLING BASIN SHALL BE REMOVED AT THE COMPLETION OF THE PROJECT. ALL DISTURBED AREAS SHALL BE RESTORED.
- E10. INSTALL EROSION CONTROLS AT THE EDGE OF PROPOSED WORK. EROSION CONTROLS SHALL ACT AS LIMIT OF WORK LINE TO HELP ENSURE THAT EQUIPMENT DOES NOT DISTURB ADJACENT PROPERTIES.
- E11. ADDITIONAL EROSION CONTROLS MAY BE REQUIRED TO PREVENT SEDIMENTS FROM DISCHARGING TO ADJACENT PROPERTIES OR INTO EXISTING STORM DRAIN SYSTEMS.
- E12. STABILIZE THE AREAS OF CONSTRUCTION ACTIVITIES AT THE CLOSE OF EACH CONSTRUCTION DAY. CHECK EROSION CONTROLS AT THIS TIME AND MAINTAIN OR REINFORCE IF NECESSARY.
- E13. PROTECT NEW WORK FROM FLOODING. PROPERLY SLOPE GRADING IN THE AREAS SURROUNDING ALL EXCAVATIONS TO PREVENT WATER FROM RUNNING INTO THE EXCAVATED AREA OR TO ADJACENT PROPERTIES. UPON COMPLETION OF THE WORK, RESTORE ALL AREAS IN A SATISFACTORY MANNER DETERMINED BY THE OWNER.
- E14. ALL SILT-LADEN WATER MUST BE SETTLED OR FILTERED TO REMOVE ALL SEDIMENTS IN A SEDIMENTATION BASIN OR FILTER BAG LOCATED DOWNSTREAM, PRIOR TO RELEASE TO A WATERWAY OR EXISTING DRAINAGE SYSTEM.
- E15. DEWATER AS NECESSARY TO KEEP CONSTRUCTION AREAS FREE OF WATER, DISCHARGE WATER FROM DEWATERING TO THE APPROPRIATE LOCATION AND WITHOUT SEDIMENT.
- E16. AT THE END OF EACH WORK DAY, ANY SEDIMENTS TRACKED ONTO PUBLIC RIGHT-OF-WAYS BEYOND THE PROJECT LIMITS SHALL BE SWEPT AWAY

BEST MANAGEMENT PRACTICES

- SEDIMENT, EROSION CONTROLS, AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE INSTALLED PRIOR TO COMMENCING CONSTRUCTION AT THE SITE. NO WORK WHICH SHALL DISTURB THE SITE OR CREATE THE POTENTIAL FOR SEDIMENT RELEASE SHALL COMMENCE UNTIL THE SEDIMENT AND EROSION CONTROLS HAVE BEEN INSPECTED AND APPROVED BY THE OWNER, ENGINEER, AND REGULATORY AGENCIES. ALL CONTROLS AND BMPS SHALL BE SUBJECT TO INSPECTION BY THE OWNER, THEIR REPRESENTATIVE, AND REGULATORY AGENCIES AT ANYTIME THEREAFTER.
- PERIODIC INSPECTION, MAINTENANCE, AND CLEANING OF TEMPORARY EROSION OF SEDIMENT CONTROL MEASURES AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE REQUIRED. ALL CONTROLS AND BMPS SHALL BE INSPECTED EVERY 7 DAYS AND WITHIN 24 HOURS OF RAINFALL EVENTS OF 0.5 INCHES OR GREATER. ROUTINE INSPECTION AND MAINTENANCE WILL REDUCE THE CHANCE OF POLLUTING STORMWATER BY FINDING AND CORRECTING PROBLEMS BEFORE THE NEXT RAIN EVENT. THE FOCUS OF THE INSPECTION WILL BE TO DETERMINE:
 - . WHETHER OR NOT THE MEASURE WAS INSTALLED / PERFORMED CORRECTLY;
 - 2. WHETHER OR NOT THERE HAS BEEN ANY DAMAGE TO THE MEASURE SINCE IT WAS INSTALLED OR PERFORMED; AND
- 3. WHAT SHOULD BE DONE TO CORRECT ANY PROBLEMS WITH THE MEASURE. EACH MEASURE IS TO BE OBSERVED TO DETERMINE IF IT IS STILL EFFECTIVE. IN SOME CASES, SPECIFIC MEASUREMENTS MAY BE TAKEN TO DETERMINE IF MAINTENANCE OF THE MEASURES IS REQUIRED.

 PRIOR TO CONSTRUCTION, A SITE MANAGER WILL BE DESIGNATED BY THE CONTRACTOR TO BE RESPONSIBLE FOR INSTALLATION, MONITORING, INSPECTION, AND CORRECTION OF **EROSION AND SEDIMENT CONTROL MEASURES**

SITE CLEARING

 DURING SITE CLEARING, EXISTING VEGETATION WITHIN THE OVERALL LIMITS OF CLEARING AND GRUBBING SHALL BE REMOVED, EXCEPT AS OTHERWISE DIRECTED. PRIOR TO ANY SITE CLEARING ACTIVITIES, SEDIMENT CONTROL BARRIERS SHALL BE PLACED ALONG THE OUTER LIMIT OF DISTURBANCE. CLEARING IS TO BE LIMITED TO THOSE AREAS OF PROPOSED WORK. DISTURBED AREAS ARE TO BE KEPT TO A MINIMUM. NO TREE WITH A BREAST HEIGHT DIAMETER OF GREATER THAN 6 INCHES SHALL BE CLEARED FROM AREAS OUTSIDE THE LIMITS OF CLEARING AND GRUBBING WITHOUT PRIOR APPROVAL FROM THE OWNER.

• COMPOST FILTER TUBE BARRIERS ARE TO BE PLACED TO TRAP SEDIMENT TRANSPORTED BY RUNOFF BEFORE IT REACHES THE DRAINAGE FEATURES, WATERBODIES, OR WETLANDS, IN ADDITION TO AREAS WHERE HIGH RUNOFF VELOCITIES OR HIGH SEDIMENT LOADS ARE EXPECTED. THE COMPOST FILTER TUBES ARE TO BE REPLACED AS DETERMINED BY PERIODIC FIELD INSPECTIONS.

DUST CONTROL

• STANDARD DUST CONTROL MEASURES, INCLUDING SPRAYING AND MISTING SHALL BE USED AS NECESSARY. CALCIUM CHLORIDE SHALL NOT BE ALLOWED ON THIS PROJECT.

- THE CONTRACTOR SHALL COORDINATE LAYDOWN STAGING AREAS IN WHICH TO STORE EQUIPMENT AND MATERIALS WITH THE OWNER.
- STAGING AREAS SHALL BE SURROUNDED WITH COMPOST FILTER TUBE EROSION BARRIERS ON THE DOWNHILL SIDE.
- DURING AND AFTER CONSTRUCTION, ALL PAVED ROAD AND DRIVEWAY SURFACES ARE TO BE SCRAPED AND BROOMED FREE OF EXCAVATED MATERIALS ON A DAILY BASIS, UNLESS APPROVED BY THE OWNER.

 STOCKPILES OF SOIL CREATED DURING CONSTRUCTION ACTIVITIES ARE TO BE SURROUNDED WITH AN EROSION CONTROL BARRIER AROUND THE PERIMETER OF THE STOCKPILE. STOCKPILES OF ERODIBLE MATERIAL ARE TO BE COVERED PRIOR TO INCLEMENT WEATHER WITH A MINIMUM OF 20 MIL POLYETHYLENE SHEETING. STOCKPILES LEFT UNDISTURBED LONGER THAN 14 DAYS SHALL BE SEEDED OR COVERED.

EQUIPMENT FUELING

 EQUIPMENT FUELING AND OTHER ACTIVITIES INVOLVING PETROLEUM, OIL, OR OTHER POTENTIALLY HAZARDOUS SUBSTANCES ARE TO BE PERFORMED AT PRE-APPROVED, DESIGNATED AREAS WITH APPROPRIATE SPILL PREVENTION AND CONTROL MEASURES. PORTABLE SECONDARY CONTAINMENT IS TO BE USED, AND SORBENT MATERIALS ARE TO BE PLACED AROUND THE PERIMETER OF THE FUELING AREA.

- CONSTRUCTION DEWATERING SHALL BE REQUIRED DURING PORTIONS OF CONSTRUCTION WHICH REQUIRE EXCAVATION OR OTHER ACTIVITIES WHERE GROUNDWATER MAY INTERFERE WITH THE WORK.
- CONSTRUCTION DEWATERING DISCHARGE TO A SURFACE WATER BODY SHALL BE PRE-TREATED FOR SEDIMENT REMOVAL BY PASSING THROUGH AN APPROPRIATELY SIZED FILTER
- SOCK, SILT BAG, FRACTIONATION / SEDIMENTATION TANK, OR SEDIMENT TRAP PRIOR TO DISCHARGE, AS NECESSARY. • THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DEWATERING TECHNIQUES AND MAINTAINING DEWATERING PROCEDURES THROUGHOUT THE DURATION OF THE PROJECT.

 APPROPRIATE OUTLET PROTECTION, CONSISTING OF RIPRAP CHANNEL LINING, A LEVEL SPREADER, OR OTHER SUCH MEASURE SHALL BE PROVIDED AT THE OUTLET OF ANY DEWATERING CONDUIT OR STORMWATER CULVERT OR CHANNEL OUTFALL TO REDUCE VELOCITIES AND ENHANCE SEDIMENTATION PRIOR TO DISCHARGE.

THE CONTRACTOR SHALL LINE THE UPGRADIENT BOUNDARY OF WORK AREAS WITH ORANGE SAFETY FENCING BEFORE THE START OF SITE CLEARING ACTIVITIES.

 THE CONTRACTOR MUST MAINTAIN THE FLOWAGE OF SURFACE WATER THROUGH THE WORK AREA IN ACCORDANCE WITH THE SPECIFICATIONS. ALL COFFERDAMS SHALL CONSIST OF NON-ERODIBLE MATERIAL. THE CONTRACTOR SHALL SUBMIT A WATER CONTROL PLAN THAT WILL ADDRESS EMERGENCY MEASURES TO IMPLEMENT IN THE EVENT A STORM OCCURS DURING CONSTRUCTION

TEMPORARY STABILIZATION

- WHEN NECESSARY, TEMPORARY SLOPE PROTECTION SHALL BE PROVIDED BY INSTALLING SEDIMENT TRAP BARRIERS AT THE TOE OF FILLS OR CUT SLOPES. IF ADDITIONAL STABILIZATION IS NEEDED, THEN THE CONTRACTOR SHALL INSTALL MULCH LOGS, MATTING, SUCH AS STRAW, JUTE, WOOD FIBER, OR BIODEGRADABLE MESH. A TACKIFIER SHALL BE USED ON LOOSE MATERIALS USED FOR TEMPORARY EROSION CONTROL
- IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN TWO WEEKS, THE AREAS SHALL BE MULCHED WITH STRAW AT A RATE OF 100 LBS. PER 1,000 S.F. TO HELP CONTROL EROSION. 100% BIODEGRADABLE EROSION CONTROL BLANKETS OR TWO INCHES OF WOOD CHIP MULCH MAY ALSO BE USED AS TEMPORARY COVER.
- IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN ONE MONTH, THE AREAS SHALL BE TOPSOILED AND SEEDED AS PER THE SPECIFICATIONS AND AT NO ADDITIONAL COST TO THE OWNER.
- LEAVE THE SURFACE OF ALL EXCAVATIONS AND FILLS IN A FIRM AND STABLE CONDITION AT THE END OF EACH DAY. ROLL OR OTHERWISE TREAT THE SURFACE AS NEEDED.

- STABILIZATION OF DISTURBED AREAS OR NEW SOIL FILLS SHALL BE IMPLEMENTED WITHIN 14 DAYS AFTER GRADING OR CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED. APPROPRIATE VEGETATIVE SOIL STABILIZATION IS TO BE USED TO MINIMIZE EROSION. TEMPORARY AND PERMANENT VEGETATIVE COVER IS TO BE ESTABLISHED IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF PREVIOUSLY VEGETATED UPLAND AREAS DISTURBED BY CONSTRUCTION ACTIVITIES. RESTORATION OF UPLAND AREAS CONSIST OF REPLACEMENT OF TOPSOIL OR PLACEMENT OF IMPORTED LOAM AS NEEDED SUCH THAT A MINIMUM OF 4 INCHES OF SUITABLE MATERIAL IS PRESENT AND APPROPRIATELY LIMED, FERTILIZED, GRADED, AND SCARIFIED. FIELDS DISTURBED OR COMPACTED BY CONSTRUCTION ACTIVITIES SHALL BE PLOWED TO LOOSEN THE SOIL, HARROWED TO PROVIDE AN EVEN SURFACE, AND APPROPRIATELY PREPARED FOR PLANTING.
- DISTURBED UPLAND AREAS SHALL THEN BE HYDROSEEDED WITH AN APPROVED SEED MIX AT THE RATE RECOMMENDED BY THE MANUFACTURER. SEEDING RATE SHALL BE DOUBLED FOR DORMANT SEEDING. SEED MIX SHALL BE DRY SITE RESTORATION SEED MIX UNLESS OTHERWISE NOTED OR AS APPROVED BY THE ENGINEER.
- 100% BIODEGRADABLE EROSION CONTROL BLANKETS MUST BE USED FOR STABILIZATION OF SLOPES IN EXCESS OF 3H:1V AND MAY BE USED IN LIEU OF HYDROSEEDING AT THE CONTRACTOR'S DISCRETION TO PROVIDE ADDITIONAL EROSION PROTECTION.
- FINAL STABILIZATION SHALL BE CONSIDERED COMPLETE WHEN ALL SOIL-DISTURBING ACTIVITIES HAVE BEEN COMPLETED AND A UNIFORM, PERENNIAL VEGETATIVE COVER WITH A DENSITY OF EIGHTY PERCENT HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS THE USE OF MULCHES OR EROSION CONTROL MATTING) HAVE BEEN EMPLOYED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL VEGETATED SURFACES, INCLUDING WATERING, FERTILIZING, REPAIRING EROSION, INVASIVE PLANT REMOVAL, AND RE-SEEDING UNTIL ESTABLISHMENT CONDITIONS ARE MET AND UNTIL THE END OF THE CONTRACTUAL MAINTENANCE PERIOD.
- EXCEPT WHERE OTHERWISE NOTED THE FOLLOWING SEED MIXES SHALL BE USED FOR FINAL SEEDING.

THE NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DRY SITES:

BOTANICAL NAME CREEPING RED FESCUE Festuca rubra CANADA WILD RYE Elymus canadensis ANNUAL RYEGRASS Lolium multiflorum PERENNIAL RYEGRASS Lolium perenne BLUE GRAMA Bouteloua gracilis LITTLE BLUESTEM Schizachyrium scoparium INDIAN GRASS Sorghastrum nutans ROUGH BENTGRASS/TICKLEGRASS Agrostis scabia **UPLAND BENTGRASS** Agrostis perennans

THE NEW ENGLAND WETLAND SEED MIX:

BOTANICAL NAME FOX SEDGE Carex vulpinoidea BLUNT BROOM SEDGE Carex scoparia BLUE VERVAIN Verbena hastata LURID SEDGE Carex lurida FOWL BLUEGRASS Poa palustris TICKSEED SUNFLOWER/BUR MARIGOLD Bidens aristosa HOP SEDGE Carex lupulina GREEN BULRUSH Scirpus atrovirens CREEPING SPIKE RUSH Eleocharis palustris SOFT RUSH Juncus effusus FRINGED SEDGE Carex crinita SWAMP MILKWEED Asclepias incarnata SWAMP ASTER Aster puniceus RATTLESNAKE GRASS Glyceria canadensis SQUARE STEMMED MONKEY FLOWER Mimulus ringens SPOTTED JOE PYE WEED Eupatorium maculatum BLUE FLAG

GENERAL NOTES:

- 1. THE EXISTING CONDITIONS PLAN IS BASED ON A PLAN TITLED "TOPOGRAPHIC SURVEY SUTTON DAM PROJECT, SUTTON, MA, PREPARED FOR TIGHE & BOND" BY BRENNAN CONSULTING, ENGINEERING, TRANSPORTATION, SURVEYING, DATED NOVEMBER 17, 2016.
- 2. THE HORIZONTAL DATUM SHOWN REFERENCES THE NORTH AMERICAN HORIZONTAL DATUM OF 1983 (NAD83).
- 3. THE VERTICAL DATUM SHOWN REFERENCES THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)
- 4. WATERS OF THE UNITED STATES (WOTUS) WERE DELINEATED BY TIGHE & BOND, IN OCTOBER 2022.
- 5. SCHOOLHOUSE POND CONTOURS REPRESENT TOP OF SEDIMENT BASED UPON A BATHYMETRIC SURVEY CONDUCTED BY CR ENVIRONMENTAL DURING THE WEEK OF OCTOBER
- 6. THE 100-YEAR FLOODING LIMIT WAS ESTABLISHED BASED ON MODELING BY TIGHE & BOND USING SCS TR-55 METHODS AS OUTLINED IN 310 CMR 10.57 (2)(a)(3).

ABBREVIATIONS

VEGETATED WETLAND CORRUGATED METAL PIPE ELEV,EL ELEVATION EDGE OF WATER ORDINARY HIGH WATER MARK TEMPORARY BENCHMARK TYP TYPICAL UP UTILITY POLE

LEGEND

////// DEMOLISH

~	LITTLITY DOLE
	UTILITY POLE
	SIGN
	MAILBOX
———— OE ————	OVERHEAD ELECTRIC LINE
	PROPOSED CULVERT LINE
	DRAIN STRUCTURE
	PROPERTY LINE
	FDGE OF PAVEMENT
	GUARDRAIL
000000000000000000000000000000000000000	
	PROPOSED CHAIN LINK FENCE
(K)	DECIDUOUS TREE
W. W.	CONIFEROUS TREE
⊕ ~~~~~	BORING
	LIMIT OF WORK
	EROSION AND SEDIMENT CONTROLS
.0000000000000	COFFERDAM
\oplus	TREE TO BE REMOVED
	PROPOSED RIP-RAP
	MINOR CONTOUR
	MAJOR CONTOUR
101	PROPOSED MINOR CONTOUR

VEGETATED WETLANDS ----- ORDINARY HIGH WATER MARK WATERS OF THE US FLAG WF—1 • . PROPOSED TREE LINE TEST PIT REQUIRED NATIVE STREAMBED MATERIAL

— · · — · · — · · — · · — EDGE OF WATER





Schoolhouse Dam Removal

Massachusetts Division of Fisheries and Wildlife

Sutton, Massachusetts

В	9/2024	Issued For Bidding
Α	4/2023	Permit Set
MARK	DATE	DESCRIPTION
PROJEC	CT NO:	M-0944-039
DATE:		9/2024
FILE:	M-0944-	-039-06-G-002-401-404.dwg

APPROVED BY: CDH GENERAL NOTES, ABBREVIATIONS, AND

GNM.I PT

DH.DRB


NO SCALE


SCALE:

DRAWN BY: CHECKED BY:

> G-002 SHEET 2 OF 17


LEGEND






9. EXCAVATE BURIED PEAT AND ORGANICS LAYERS BELOW PROPOSED STRUCTURES PRIOR TO BACKFILL.

Tighe&Bond





Schoolhouse **Dam Removal**


Massachusetts Division of Fisheries and

Massachusetts

·		
·		
В	9/2024	Issued For Bidding
Α	4/2023	Permit Set
MARK	DATE	DESCRIPTION
PROJECT NO:		M-0944-039
DATE:		9/2024
FILE:	M-0	944-039-06-C-102.dwg


SEDIMENT, AND WATER CONTROL PLAN


SHEET 4 OF 17



3. EXCAVATE BURIED PEAT AND ORGANICS LAYERS BELOW STRUCTURES PRIOR TO BACKFILL.

Tighe&Bond





Schoolhouse Dam Removal Project

Massachusetts
Division of
Fisheries and
Wildlife

Sutton, Massachusetts

В	9/2024	Issued For Bidding
Α	4/2023	Permit Set
MARK	DATE	DESCRIPTION
PROJECT NO:		M-0944-039
DATE:		9/2024
FILE:	M-0)944-039-06-C-103.dwg
DRAWN BY:		GNM,LPT


PROPOSED CONDITIONS PLAN


DH,DRB


CDH


SCALE:


C-103
SHEET 5 OF 17











- NOTES:

 1. COORDINATE ANCHOR INSTALLATION WITH PRECASTER. IF ANCHORS ARE POST-INSTALLED, LOCATE REINFORCING STEEL PRIOR TO DRILLING.

 2. CONTROLLED SHALL BE GALVANIZED AND PVC COATED
- 2. ALL COMPONENTS SHALL BE GALVANIZED AND PVC COATED

CHAIN-LINK FENCE NO SCALE

CONSTRUCTION 12' 2.0% $-1rac{1}{2}$ " HOT MIX ASPHALT TOP COURSE $-2\frac{1}{2}$ " HOT MIX ASPHALT BINDER COURSE lacksquare 12" PROCESSED GRAVEL BORROW (8" OVER CULVERT)


ROADWAY CROSS SECTION NO SCALE

* TOLERANCE FOR CONSTRUCTION ±.5%

- NOTES:

 1. ROAD WIDTH AND SLOPE SHOWN SHALL BE CONSIDERED TYPICAL.


 ON THE TOTAL TO MATCH EXISTING CONDITIONS ARE FIELD MODIFICATIONS TO MATCH EXISTING CONDITIONS ARE ANTICIPATED.
- 2. TACK COAT APPLIED AT 0.05 GAL/SY BETWEEN LIFTS.





RIP-RAP INSTALLATION/SLOPE PROTECTION NO SCALE

NOTES:

1. ALL RIPRAP TO BE UNDERLAID WITH CRUSHED STONE AND GEOTEXTILE AS SHOWN.

















Schoolhouse Dam Removal **Project**

Massachusetts Division of Fisheries and Wildlife


Sutton, Massachusetts

В	9/2024	Issued For Bidding
A	4/2023	Permit Set
RK	DATE	DESCRIPTION
OJE(CT NO:	M-0944-039
TE:		9/2024
LE:	M-0	944-039-06-C-202.dwg
RAWN BY:		GNM,LPT
IECKED BY:		DH,DRB
PRO	VED BY:	CDH
	•	•

MISCELLANEOUS DETAILS


AS SHOWN

C-202 SHEET 10 OF 17



TEMPORARY SANDBAG COFFER DAM DIVERSION PIPING


NO SCALE




GENERAL NOTES:

- 1. PROVIDE A MINIMUM TUBE DIAMETER OF 12" FOR SLOPES UP TO 50' IN LENGTH WITH A SLOPE RATIO OF 3H:1V OR STEEPER. LONGER SLOPES OF 3H:1V MAY REQUIRE LARGER TUBE DIAMETER OR ADDITIONAL COURSING OF FILTER TUBES TO CREATE A FILTER BERM. REFER TO MANUFACTURER'S RECOMMENDATIONS FOR SITUATION WITH LONGER SLOPES OR STEEPER SLOPES.
- 2. INSTALL TUBES ALONG CONTOURS AND PERPENDICULAR TO SHEET OR CONCENTRATED FLOW.
- 3. DO NOT INSTALL IN PERENNIAL, EPHEMERAL OR INTERMITTENT STREAMS.
- 4. CONFIGURE TUBES AROUND EXISTING SITE FEATURES TO MINIMIZE SITE DISTURBANCE AND MAXIMIZE CAPTURE AREA OF STORMWATER RUN-OFF.
- 5. TUBES FOR COMPOST FILTERS SHALL BE JUTE MESH OR APPROVED BIODEGRADABLE MATERIAL. ADDITIONAL TUBES SHALL BE USED AT THE DIRECTION OF THE ENGINEER.
- 6. TAMP TUBES IN PLACE TO ENSURE GOOD CONTACT WITH SOIL SURFACE. IT IS NOT NECESSARY TO TRENCH TUBES INTO EXISTING GRADE.
- 7. WHEN STAKING IS NOT POSSIBLE, SUCH AS WHEN TUBES MUST BE PLACED ON PAVEMENT, HEAVY CONCRETE OR CINDER BLOCKS CAN BE USED BEHIND TUBES UP TO 5' APART OR AS REQUIRED TO SECURE TUBES IN PLACE.

COMPOST FILTER TUBES
NO SCALE






OTES:

DEWATERING EQUIPMENT SHALL REMAIN WITHIN THE COFFER
DAM AND EROSION CONTROL MEASURES, AND SHALL DISCHARGE
OUTSIDE OF THE WETLAND BOUNDARY.

2. DISCHARGE HOSE SHALL NOT CROSS THE STREAM AT ANY LOCATION.

COFFERDAM AND DEWATERING
NO SCALE




NOTES:

- 1. EROSION CONTROL BLANKET SHOULD BE INSTALLED VERTICALLY DOWNSLOPE.
- STAKES/STAPLES SHOULD BE PLACED NO MORE THAN 3 FT APART VERTICALLY, AND 1 FT APART HORIZONTALLY.
- 3. SLOPE SURFACE SHOULD BE FREE OF STICKS, ROCKS, AND OTHER OBSTRUCTIONS.
- 4. BLANKETS SHOULD BE ROLLED OUT LOOSELY AND STAKED/STAPLED TO MAINTAIN DIRECT SOIL CONTACT. DO NOT STRETCH THE BLANKETS.

100% BIODEGRADABLE EROSION CONTROL BLANKET

NO SCALE

Tighe&Bond





Schoolhouse Dam Removal Project

Massachusetts
Division of
Fisheries and
Wildlife


Sutton, Massachusetts


}	9/2024	Issued For Bidding
١	4/2023	Permit Set
RK	DATE	DESCRIPTION
OJECT NO:		M-0944-039
TE:		9/2024
E: M-0)944-039-06-C-203.dwg
AWN BY:		GNM,LPT
ECKED BY:		DH,DRB
PROVED BY:		CDH


EROSION, SEDIMENT, AND WATER CONTROL DETAILS

SCALE: AS SHOWN


C-203










AS SHOWN








GUARDRAIL, TL-2 DETAILS TO SPAN OVER CULVERT







NOTES:

- 1. DRIVE ONE NAIL PER W BEAM TIMBER OFFSET BLOCK TO PREVENT BLOCK ROTATION. USE ASTM A153 HOT DIP GALVANIZED STEEL 3 ½" TYPE 16D NAILS. FOR STEEL POSTS, DRIVE THE NAIL THROUGH THE UNUSED FLANGE BOLT HOLE AND BEND THE NAIL SO ITS HEAD CONTACTS THE FLANGE.
- 2. DEEP STEEL POSTS SHALL ONLY BE USED WHERE INDICATED IN THESE STANDARDS OR THE PLANS.
- 3. WHERE BACK OF POSTS ARE EXPOSED AND PLACED WITHIN 2'-0" OF A SIDEWALK, SEPARATED BIKE FACILITY OR SHARED-USE PATH, TIMBER POSTS SHALL BE USED. ALTERNATIVELY, STEEL POSTS WITH A TIMBER BACKING, PER 400.5.1, MAY BE SUBSTITUTED AT NO ADDITIONAL COST. WHEN TIMBER POSTS ARE USED, ONE OF THE FOLLOWING SAFETY TREATMENTS IS REQUIRED FOR ALL BOLTS PROTRUDING FROM THE BACK FACE OF THE POST:
 - A. AFTER TIGHTENING THE NUT, TRIM THE PROTRUDING POST BOLT FLUSH WITH THE NUT AND GALVANIZE PER M7.04.11;
 - B. USE 15" POST BOLTS AND COUNTERSINK THE WASHER AND NUT BETWEEN 1" AND $1\frac{1}{2}$ " DEEP INTO THE BACK FACE OF THE POST; OR
 - C. USE 15" POST BOLT SLEEVE NUTS AND WASHERS.

END TREATMENTS AND TRANSITIONS, WHERE SPECIFIC MATERIAL TYPES ARE SPECIFIED, ARE EXEMPT FROM THESE REQUIREMENTS.





4 ½" —

W-BEAM TIMBER OFFSET BLOCK
FOR USE WITH STEEL POSTS
(6"X8" NOMINAL)

MASSDOT STANDARD DETAILS:

MASSDOT HIGHWAY DIVISION


CONSTRUCTION STANDARD DETAILS


GUARDRAIL, TL2 & W-BEAM PANEL DETAILS

W-BEAM & THRIE BEAM STEEL POST

POST & OFFSET BLOCK DETAILS







Schoolhouse Dam Removal Project

Massachusetts
Division of
Fisheries and
Wildlife

Sutton, Massachusetts

Ą	9/2024	Issued For Bidding
RK	DATE	DESCRIPTION
OJECT NO:		M-0944-039
TE:		9/2024
LE:	M-0944-	039-06-MaDOT-DETAILS.dw

APPROVED BY: CDH
HIGHWAY GUARDRAIL

GNM,LPT

DH,DRB

DETAILS (SHEET 2 OF 2)

SCALE: NO SCALE

DRAWN BY:

CHECKED BY:

C-208
SHEET 16 OF 17


FLARED END TREATMENT SEGMENT - PLAN


NOTES:

- 1. INSTALL GUARDRAIL AT STATION AND OFFSET SHOWN IN THE PLANS. THE END OF THE GUARDRAIL SHOWN IN THE PLANS CORRESPONDS WITH THE BEGIN LENGTH OF NEED POINT FOR THE END TREATMENT (SHOWN AT POST 3 IN THESE STANDARDS, BUT MAY VARY BY MANUFACTURER).
- 2. PROPRIETARY END TREATMENTS MAY VARY IN SIZE AND SHAPE FROM WHAT IS DEPICTED IN THESE STANDARDS. HOWEVER. THE MAXIMUM SLOPES AND MINIMUM OFFSETS DIMENSIONED FROM THE POSTS SHOWN HEREIN SHALL STILL APPLY.
- 3. END TREATMENT TEST LEVEL AND TYPE (TANGENT OR FLARED) SHALL BE SPECIFIED IN THE PLANS.
- 4. CONSTRUCT TANGENT AND FLARED END TREATMENTS IN ACCORDANCE WITH THE MANUFACTURER'S UNIQUE DRAWING DETAILS, PROCEDURES, AND SPECIFICATIONS.
- 5. AT THE DISCRETION OF THE ENGINEER, THE FACE OF THE TANGENT END TREATMENT IMPACT HEAD MAY BE OFFSET UP TO 2'-0" FROM THE PROJECTED FACE OF GUARDRAIL TO MINIMIZE NUISANCE HITS. THE OFFSET SHALL OCCUR OVER THE ENTIRE LENGTH OF THE END TREATMENT UNLESS OTHERWISE SPECIFIED BY THE
- 6. LATERAL OFFSET OF FLARED END TREATMENT SHALL BE DETERMINED BY THE DESIGN ENGINEER FOLLOWING THE METHODOLOGY FOUND IN THE ROADSIDE DESIGN GUIDE AND SHOULD FALL WITHIN THE ALLOWABLE TOLERANCES SPECIFIED BY THE MANUFACTURER. LATERAL OFFSET SHALL BE MEASURED FROM THE EDGE OF TRAVELED WAY TO THE FACE OF THE GUARDRAIL AT POST #3.
- 7. END TREATMENTS SHALL NOT TERMINATE CURVED W-BEAM SEGMENTS.
- 8. END TREATMENT IMPACT HEAD DELINEATION SHALL CONFORM TO 601.63.
- 9. INSTALL GRADING AS SHOWN HEREIN UNDER SEPARATE PAY ITEMS.
- 10. SEE 400.2.2 FOR APPROACH TERMINAL GEOMETRY FOR GUARDRAIL INSTALLED ADJACENT TO CURB AND DOUBLE FACED GUARDRAIL.
- 11. MAINTAIN 2'-0" (MIN) OFFSET TO FRONT SLOPE BREAK DOWNSTREAM OF MIDSPAN SPLICE LOCATION AT ALL TIMES. IF, DOWNSTREAM OF THE SPLICE, GRADING CONSTRAINTS INHIBIT THIS MINIMUM OFFSET THEN USE DEEP STEEL POSTS AND TRANSITION TO A SLOPE BREAK CONDITION DESIGN PER THE DETAIL IN 400.1.5 UNTIL THE 2'-0" OFFSET CAN BE MET.


NOTES:

- 1. ALL DIMENSIONS OF STANDARD GUARDRAIL COMPONENTS, INCLUDING PANELS, POSTS, OFFSET BLOCKS, BOLTS, NUTS, WASHERS AND HOLES, ARE BASED UPON ENGLISH UNIT CONVERSIONS OF THE AASHTO-ARTBA-AGC JOINT COMMITTEE TASK FORCE 13 REPORT: A GUIDE TO STANDARDIZING HIGHWAY BARRIER HARDWARE (http://www.aashtotf13.org/Barrier-Hardware.php).
- 2. ALL GUARDRAIL MATERIALS SHALL CONFORM TO M8.07.0 UNLESS OTHERWISE INDICATED.
- 3. APPROVAL BY THE ENGINEER IS REQUIRED WHERE A DIFFERING GUARDRAIL CONFIGURATION IS REQUIRED FOR CONSTRUCTABILITY BEYOND THE OPTIONS SHOWN IN THESE STANDARDS OR THE PLANS.
- 4. THE BEGIN OR END STATION LABELS SHOWN IN THESE STANDARDS CORRESPOND TO THE STATION AND OFFSET CALLOUTS SPECIFIED IN THE PLANS.
- 5. USE 12'-6" NOMINAL LENGTH PANELS UNLESS OTHERWISE INDICATED IN THESE STANDARDS OR THE PLANS.
- 6. ALL LAP SPLICES SHALL BE MIDSPAN UNLESS OTHERWISE SHOWN.
- 7. LAP SPLICES SHALL BE CONSTRUCTED WITH THE SPLICE RIDGE ORIENTED DOWNSTREAM OF THE FINAL DIRECTION OF TRAFFIC IN THE NEAREST TRAVEL LANE. REORIENTING LAP SPLICES FOR TEMPORARY TRAFFIC CONTROL IS NOT REQUIRED.
- 8. STANDARD POSTS SHALL BE STEEL OR TIMBER, UNLESS OTHERWISE INDICATED IN THE PLANS, FABRICATED TO THE DIMENSIONS SHOWN ON 400.1.4. POSTS OF A SINGLE MATERIAL TYPE SHALL BE USED THROUGHOUT AN ENTIRE RUN OF GUARDRAIL; EXCEPTIONS ARE ALLOWED ONLY WHEN SPECIFIC MATERIAL TYPES ARE REQUIRED FOR TRANSITIONS, END TREATMENTS, AND/OR ANCHORAGES.
- 9. DEEP POST SHALL ONLY BE USED WHERE INDICATED IN THESE STANDARDS OR THE PLANS.
- 10. OFFSET BLOCKS, WHERE REQUIRED, SHALL BE TIMBER AND FABRICATED TO THE NOMINAL DIMENSIONS SHOWN ON 400.1.4. PLASTIC OR COMPOSITE OFFSET BLOCKS OF THE SAME NOMINAL DIMENSIONS THAT ARE LISTED ON THE QUALIFIED CONSTRUCTION MATERIALS LIST MAY BE SUBSTITUTED. OFFSET BLOCKS OF A SINGLE MATERIAL TYPE SHALL BE USED THROUGHOUT AN ENTIRE RUN OF GUARDRAIL; EXCEPTIONS ARE ALLOWED ONLY WHEN SPECIFIC MATERIAL TYPES ARE REQUIRED FOR TRANSITIONS, END TREATMENTS, AND/OR ANCHORAGES.
- 11. PAVEMENT MILLING MULCH, WHERE CALLED FOR IN THE STANDARDS, SHALL CONFORM TO SECTION 739.
- 12. GUARDRAIL DELINEATORS, CONFORMING TO SECTION 601, SHALL BE INSTALLED AT 25' INTERVALS WITHIN 100' OF AN END TREATMENT OR TRAILING ANCHORAGE AND AT 100' INTERVALS IN ALL OTHER AREAS UNLESS OTHERWISE SHOWN IN THE PLANS.
- 13. MINIMUM OFFSET DISTANCE FROM FACE OF W-BEAM PANEL TO A FIXED (NON-BREAKAWAY) OBJECT SHALL BE 48" FOR TL-2 AND 60" FOR TL-3.





PLAN



CHANNEL STRUT

NOTES:


- FOR ADDITIONAL DETAILS, SEE 400.4.2.
- 2. LAP THE ROUNDED END UNIT OVER THE FACE OF THE W-BEAM PANEL.
- 3. INSTALL STEEL TUBE FOUNDATIONS BY ONE OF THE FOLLOWING METHODS:


ELEVATION

ROUNDED END UNIT

- 15 X 1 1 SLOTS (TYP)(4 REQD.)

- A. EXCAVATE, INSTALL TUBE, BACKFILL, AND SUITABLY COMPACT MATERIALS; OR
- B. DRIVE THE TUBE USING A DUMMY TIMBER POST TO PREVENT DAMAGE TO THE SHORT BREAKAWAY POST.








ELEVATION


SHELF ANGLE BRACKET

SECTION











POST & CABLE MOUNT ASSEMBLY





CABLE ANCHOR PLATE


CABLE ANCHOR PLATE ASSEMBLY

NOTES:

- 1. COMPONENTS SHALL BE INSTALLED PER 400.4.1.
- 2. HEX NUTS, HEX JAM NUTS AND WASHERS SHALL BE IN ACCORDANCE WITH AASHTO-ARTBA-AGC A GUIDE TO STANDARDIZING HIGHWAY BARRIER HARDWARE. TWO HEX NUTS MAY BE USED FOR THE HEX JAM SYSTEM.
- 3. DRIVE TWO ASTM A153 HOT DIP GALVANIZED STEEL 2 ½" TYPE 8D NAILS TO PREVENT ROTATION OF THE BCT BEARING PLATE.

MASSDOT STANDARD DETAILS: MASSDOT 2017 CONSTRUCTION STANDARD DETAILS, 400.1.0, 400.3.6, 400.4.1, 400.4.2

Tighe&Bond





Schoolhouse Dam Removal **Project**

Massachusetts Division of Fisheries and Wildlife

Sutton, Massachusetts

Α	9/2024	Issued For Bidding
1ARK	DATE	DESCRIPTION
PROJECT NO:		M-0944-039
DATE:		9/2024
FILE:	M-0944-	039-06-MaDOT-DETAILS.dwg
DRAWN BY:		GNM,LPT
CHECKED BY:		DH.DRB

GUARDRAIL APPROACH GEOMETRY

CDH


APPROVED BY:

NO SCALI SCALE:

C-209 SHEET 17 OF 17

MASSACHUSETTS DIVISION OF FISHERIES AND WILDLIFE ARNOLD POND DAM REMOVAL PROJECT SUTTON, MASSACHUSETTS OCTOBER 2024

INDEX OF SHEETS		
SHEET	SHEET NUMBER	SHEET TITLE
		GENERAL
1	G-001	COVER SHEET
2	G-002	GENERAL NOTES, ABBREVIATIONS, AND LEGEND
CIVIL		
3	C-101	EXISTING CONDITIONS PLAN
4	C-102	SITE PREPARATION AND DEMOLITION PLAN
5	C-103	PROPOSED CONDITIONS PLAN
6	C-201	EROSION, SEDIMENT, AND WATER CONTROL DETAILS
7	C-202	MISCELLANEOUS DETAILS
STRUCTURAL		
8	S-201	PEDESTRIAN BRIDGE PLAN AND PROFILE VIEW
9	S-202	PEDESTRIAN BRIDGE AND ABUTMENT DETAILS




LOCATION MAP


SCALE: 1" = 2000'

PREPARED BY:

Tighe&Bond







DANIEL R. HAMMERBERG, PE

PREPARED FOR:

MASSACHUSETTS DIVISION OF FISHERIES & WILDLIFE

CALEB SLATER, PhD, CHIEF OF HATCHERIES

COMPLETE SET 9 SHEETS

EROSION AND SEDIMENTATION CONTROL NOTES:

- TEMPORARY SEDIMENT AND EROSION CONTROL BY THE CONTRACTOR SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATIONS LISTED BELOW
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING ALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES NECESSARY TO EXECUTE AND COMPLETE THE WORK OF THE CONTRACT, IN COMPLIANCE WITH THE TERMS AND CONDITIONS CONTAINED IN THE CONTRACT AND PROJECT PERMITS. CONTROLS SHOWN ON THE CONTRACT DRAWINGS AND MENTIONED IN THE TECHNICAL SPECIFICATIONS SHALL BE CONSIDERED MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL EMPLOY WHATEVER SUPPLEMENTARY MEASURES NECESSARY TO PROTECT WETLANDS, WATERS, AND ADJACENT AREAS FROM DISTURBANCE OR DISCHARGE OF SEDIMENTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SEDIMENT AND EROSION CONTROLS TO MEET THE CONDITIONS OF ALL APPLICABLE PERMITS AND REGULATIONS. SUCH CONTROLS SHALL BE INSTALLED WHEREVER THE POTENTIAL EXISTS FOR THE DISTURBANCE OF LAND OR THE TRANSPORT OF SEDIMENT.
- EROSION AND SEDIMENTATION PERIMETER CONTROLS SHALL CONSIST OF 100% BIODEGRADABLE COMPOST FILTER TUBES INSTALLED PER DETAILS PROVIDED ON SHEET C-201. PLASTIC MESH MATERIALS SHALL NOT BE PERMITTED.
- COMPOST FILTER TUBES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF CLEARING AND GRUBBING ACTIVITIES. LOCATION OF COMPOST FILTER TUBES TO BE ADJUSTED UPON COMPLETION OF CLEARING AND GRUBBING BUT PRIOR TO COMMENCEMENT OF GRADING ACTIVITIES
- ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE MAINTAINED IN GOOD CONDITION AND PROPER WORKING ORDER. NECESSARY REPAIRS SHALL BE MADE IMMEDIATELY.
- ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE PROPERLY DISPOSED OFF-SITE UPON COMPLETION OF WORK, SITE STABILIZATION AND/OR AUTHORIZATION FROM THE OWNER.
- MAINTAIN AN ADDITIONAL SUPPLY OF EROSION CONTROL MEASURES ONSITE THROUGHOUT THE CONSTRUCTION PERIOD.
- SILT TRAPPED AT BARRIERS SHALL BE REMOVED AND DISPOSED OF IN UPLAND AREAS OUTSIDE BUFFER ZONES. MATERIALS DEPOSITED IN ANY TEMPORARY SETTLING BASIN SHALL BE REMOVED AT THE COMPLETION OF THE PROJECT. ALL DISTURBED AREAS SHALL BE RESTORED.
- E10. INSTALL EROSION CONTROLS AT THE EDGE OF PROPOSED WORK. EROSION CONTROLS SHALL ACT AS LIMIT OF WORK LINE TO HELP ENSURE THAT EQUIPMENT DOES NOT DISTURB ADJACENT PROPERTIES
- E11. ADDITIONAL EROSION CONTROLS MAY BE REQUIRED TO PREVENT SEDIMENTS FROM DISCHARGING TO ADJACENT PROPERTIES OR INTO EXISTING STORM DRAIN SYSTEMS.
- E12. STABILIZE THE AREAS OF CONSTRUCTION ACTIVITIES AT THE CLOSE OF EACH CONSTRUCTION DAY. CHECK EROSION CONTROLS AT THIS TIME AND MAINTAIN OR REINFORCE IF NECESSARY.
- E13. PROTECT NEW WORK FROM FLOODING. PROPERLY SLOPE GRADING IN THE AREAS SURROUNDING ALL EXCAVATIONS TO PREVENT WATER FROM RUNNING INTO THE EXCAVATED AREA OR TO ADJACENT PROPERTIES. UPON COMPLETION OF THE WORK, RESTORE ALL AREAS IN A SATISFACTORY MANNER DETERMINED BY THE OWNER.
- E14. ALL SILT-LADEN WATER MUST BE SETTLED OR FILTERED TO REMOVE ALL SEDIMENTS IN A SEDIMENTATION BASIN OR FILTER BAG LOCATED DOWNSTREAM, PRIOR TO RELEASE TO A WATERWAY OR EXISTING DRAINAGE SYSTEM.
- E15. DEWATER AS NECESSARY TO KEEP CONSTRUCTION AREAS FREE OF WATER, DISCHARGE WATER FROM DEWATERING TO THE APPROPRIATE LOCATION AND WITHOUT SEDIMENT.
- E16. AT THE END OF EACH WORK DAY, ANY SEDIMENTS TRACKED ONTO PUBLIC RIGHT-OF-WAYS BEYOND THE PROJECT LIMITS SHALL BE SWEPT AWAY.

BEST MANAGEMENT PRACTICES

INSPECTION AND MAINTENANCE

- SEDIMENT, EROSION CONTROLS, AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE INSTALLED PRIOR TO COMMENCING CONSTRUCTION AT THE SITE. NO WORK WHICH SHALL DISTURB THE SITE OR CREATE THE POTENTIAL FOR SEDIMENT RELEASE SHALL COMMENCE UNTIL THE SEDIMENT AND EROSION CONTROLS HAVE BEEN INSPECTED AND APPROVED BY THE OWNER, ENGINEER, AND REGULATORY AGENCIES. ALL CONTROLS AND BMPS SHALL BE SUBJECT TO INSPECTION BY THE OWNER, THEIR REPRESENTATIVE, AND REGULATORY AGENCIES AT ANYTIME THEREAFTER.
- PERIODIC INSPECTION, MAINTENANCE, AND CLEANING OF TEMPORARY EROSION OF SEDIMENT CONTROL MEASURES AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE REQUIRED. ALL CONTROLS AND BMPS SHALL BE INSPECTED EVERY 7 DAYS AND WITHIN 24 HOURS OF RAINFALL EVENTS OF 0.5 INCHES OR GREATER. ROUTINE INSPECTION AND MAINTENANCE WILL REDUCE THE CHANCE OF POLLUTING STORMWATER BY FINDING AND CORRECTING PROBLEMS BEFORE THE NEXT RAIN EVENT. THE FOCUS OF THE INSPECTION WILL BE TO DETERMINE:
 - WHETHER OR NOT THE MEASURE WAS INSTALLED / PERFORMED CORRECTLY;
- WHETHER OR NOT THERE HAS BEEN ANY DAMAGE TO THE MEASURE SINCE IT WAS INSTALLED OR PERFORMED; AND
- 3. WHAT SHOULD BE DONE TO CORRECT ANY PROBLEMS WITH THE MEASURE. EACH MEASURE IS TO BE OBSERVED TO DETERMINE IF IT IS STILL EFFECTIVE. IN SOME CASES, SPECIFIC MEASUREMENTS MAY BE TAKEN TO DETERMINE IF MAINTENANCE OF THE MEASURES IS REQUIRED.

 PRIOR TO CONSTRUCTION, A SITE MANAGER WILL BE DESIGNATED BY THE CONTRACTOR TO BE RESPONSIBLE FOR INSTALLATION, MONITORING, INSPECTION, AND CORRECTION OF **EROSION AND SEDIMENT CONTROL MEASURES**

DURING SITE CLEARING, EXISTING VEGETATION WITHIN THE OVERALL LIMITS OF CLEARING AND GRUBBING SHALL BE REMOVED, EXCEPT AS OTHERWISE DIRECTED. PRIOR TO ANY SITE CLEARING ACTIVITIES, SEDIMENT CONTROL BARRIERS SHALL BE PLACED ALONG THE OUTER LIMIT OF DISTURBANCE. CLEARING IS TO BE LIMITED TO THOSE AREAS OF PROPOSED WORK. DISTURBED AREAS ARE TO BE KEPT TO A MINIMUM. NO TREE SHALL BE CLEARED FROM AREAS OUTSIDE THE LIMITS OF CLEARING AND GRUBBING WITHOUT PRIOR

EROSION CONTROL BARRIERS

 COMPOST FILTER TUBE BARRIERS ARE TO BE PLACED TO TRAP SEDIMENT TRANSPORTED BY RUNOFF BEFORE IT REACHES THE DRAINAGE FEATURES, WATERBODIES, OR WETLANDS, IN ADDITION TO AREAS WHERE HIGH RUNOFF VELOCITIES OR HIGH SEDIMENT LOADS ARE EXPECTED. THE COMPOST FILTER TUBES ARE TO BE REPLACED AS DETERMINED BY PERIODIC FIELD INSPECTIONS.

• STANDARD DUST CONTROL MEASURES, INCLUDING SPRAYING AND MISTING SHALL BE USED AS NECESSARY. CALCIUM CHLORIDE SHALL NOT BE ALLOWED ON THIS PROJECT.

- THE CONTRACTOR SHALL COORDINATE LAYDOWN STAGING AREAS IN WHICH TO STORE EQUIPMENT AND MATERIALS WITH THE OWNER.
- STAGING AREAS SHALL BE SURROUNDED WITH COMPOST FILTER TUBE EROSION BARRIERS ON THE DOWNHILL SIDE.
- DURING AND AFTER CONSTRUCTION, ALL PAVED ROAD AND DRIVEWAY SURFACES ARE TO BE SCRAPED AND BROOMED FREE OF EXCAVATED MATERIALS ON A DAILY BASIS, UNLESS

STOCKPILED MATERIALS

 STOCKPILES OF SOIL CREATED DURING CONSTRUCTION ACTIVITIES ARE TO BE SURROUNDED WITH AN EROSION CONTROL BARRIER AROUND THE PERIMETER OF THE STOCKPILE. STOCKPILES OF ERODIBLE MATERIAL ARE TO BE COVERED PRIOR TO INCLEMENT WEATHER WITH A MINIMUM OF 20 MIL POLYETHYLENE SHEETING. STOCKPILES LEFT UNDISTURBED LONGER THAN 14 DAYS SHALL BE SEEDED OR COVERED.

 EQUIPMENT FUELING AND OTHER ACTIVITIES INVOLVING PETROLEUM, OIL, OR OTHER POTENTIALLY HAZARDOUS SUBSTANCES ARE TO BE PERFORMED AT PRE-APPROVED, DESIGNATED AREAS WITH APPROPRIATE SPILL PREVENTION AND CONTROL MEASURES. PORTABLE SECONDARY CONTAINMENT IS TO BE USED, AND SORBENT MATERIALS ARE TO BE PLACED AROUND THE PERIMETER OF THE FUELING AREA.

CONSTRUCTION DEWATERING

- CONSTRUCTION DEWATERING SHALL BE REQUIRED DURING PORTIONS OF CONSTRUCTION WHICH REQUIRE EXCAVATION OR OTHER ACTIVITIES WHERE GROUNDWATER MAY
- CONSTRUCTION DEWATERING DISCHARGE TO A SURFACE WATER BODY SHALL BE PRE-TREATED FOR SEDIMENT REMOVAL BY PASSING THROUGH AN APPROPRIATELY SIZED FILTER
- SOCK, SILT BAG, FRACTIONATION / SEDIMENTATION TANK, OR SEDIMENT TRAP PRIOR TO DISCHARGE, AS NECESSARY. • THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DEWATERING TECHNIQUES AND MAINTAINING DEWATERING PROCEDURES THROUGHOUT THE DURATION OF THE PROJECT.

OUTLET PROTECTION

• APPROPRIATE OUTLET PROTECTION, CONSISTING OF RIPRAP CHANNEL LINING, A LEVEL SPREADER, OR OTHER SUCH MEASURE SHALL BE PROVIDED AT THE OUTLET OF ANY DEWATERING CONDUIT OR STORMWATER CULVERT OR CHANNEL OUTFALL TO REDUCE VELOCITIES AND ENHANCE SEDIMENTATION PRIOR TO DISCHARGE.

LIMITS OF WORK

• THE CONTRACTOR SHALL LINE THE UPGRADIENT BOUNDARY OF WORK AREAS WITH ORANGE SAFETY FENCING BEFORE THE START OF SITE CLEARING ACTIVITIES.

SURFACE WATER CONTRO

 THE CONTRACTOR MUST MAINTAIN THE FLOWAGE OF SURFACE WATER THROUGH THE WORK AREA IN ACCORDANCE WITH THE SPECIFICATIONS. ALL COFFERDAMS SHALL CONSIST OF NON-ERODIBLE MATERIAL. THE CONTRACTOR SHALL SUBMIT A WATER CONTROL PLAN THAT WILL ADDRESS EMERGENCY MEASURES TO IMPLEMENT IN THE EVENT A STORM OCCURS DURING CONSTRUCTION.

- WHEN NECESSARY, TEMPORARY SLOPE PROTECTION SHALL BE PROVIDED BY INSTALLING SEDIMENT TRAP BARRIERS AT THE TOE OF FILLS OR CUT SLOPES. IF ADDITIONAL STABILIZATION IS NEEDED, THEN THE CONTRACTOR SHALL INSTALL MULCH LOGS, MATTING, SUCH AS STRAW, JUTE, WOOD FIBER, OR BIODEGRADABLE MESH. A TACKIFIER SHALL BE USED ON LOOSE MATERIALS USED FOR TEMPORARY EROSION CONTROL
- IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN TWO WEEKS, THE AREAS SHALL BE MULCHED WITH STRAW AT A RATE OF 100 LBS. PER
- 1,000 S.F. TO HELP CONTROL EROSION. 100% BIODEGRADABLE EROSION CONTROL BLANKETS OR TWO INCHES OF WOOD CHIP MULCH MAY ALSO BE USED AS TEMPORARY COVER. • IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN ONE MONTH, THE AREAS SHALL BE TOPSOILED AND SEEDED AS PER THE SPECIFICATIONS AND AT NO ADDITIONAL COST TO THE OWNER.
- LEAVE THE SURFACE OF ALL EXCAVATIONS AND FILLS IN A FIRM AND STABLE CONDITION AT THE END OF EACH DAY. ROLL OR OTHERWISE TREAT THE SURFACE AS NEEDED.

- STABILIZATION OF DISTURBED AREAS OR NEW SOIL FILLS SHALL BE IMPLEMENTED WITHIN 14 DAYS AFTER GRADING OR CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED APPROPRIATE VEGETATIVE SOIL STABILIZATION IS TO BE USED TO MINIMIZE EROSION. TEMPORARY AND PERMANENT VEGETATIVE COVER IS TO BE ESTABLISHED IN ACCORDANCE WITH
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF PREVIOUSLY VEGETATED UPLAND AREAS DISTURBED BY CONSTRUCTION ACTIVITIES. RESTORATION OF UPLAND AREAS CONSIST OF REPLACEMENT OF TOPSOIL OR PLACEMENT OF IMPORTED LOAM AS NEEDED SUCH THAT A MINIMUM OF 4 INCHES OF SUITABLE MATERIAL IS PRESENT AND APPROPRIATELY LIMED, FERTILIZED, GRADED, AND SCARIFIED. FIELDS DISTURBED OR COMPACTED BY CONSTRUCTION ACTIVITIES SHALL BE PLOWED TO LOOSEN THE SOIL, HARROWED TO PROVIDE AN EVEN SURFACE, AND APPROPRIATELY PREPARED FOR PLANTING.
- DISTURBED UPLAND AREAS SHALL THEN BE HYDROSEEDED WITH AN APPROVED SEED MIX AT THE RATE RECOMMENDED BY THE MANUFACTURER. SEEDING RATE SHALL BE DOUBLED FOR DORMANT SEEDING. SEED MIX SHALL BE THE FOLLOWING UNLESS OTHERWISE NOTED OR AS APPROVED BY THE ENGINEER

THE NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DRY SITES:

BOTANICAL NAME CREEPING RED FESCUE Festuca rubra CANADA WILD RYE Elymus canadensis ANNUAL RYEGRASS Lolium multiflorum PERENNIAL RYEGRASS Lolium perenne Bouteloua gracilis BLUE GRAMA Schizachyrium scoparium LITTLE BLUESTEM Sorghastrum nutans INDIAN GRASS Agrostis scabia ROUGH BENTGRASS/TICKLEGRASS Agrostis perennans **UPLAND BENTGRASS**

DAMP, WET, OR WETLAND ARES: THE NEW ENGLAND WETLAND SEED MIX:

BOTANICAL NAME FOX SEDGE Carex vulpinoided **BLUNT BROOM SEDGE** Carex scoparia BLUE VERVAIN Verbena hastata LURID SEDGE Carex lurida FOWL BLUEGRASS Poa palustris TICKSEED SUNFLOWER/BUR MARIGOLD Bidens aristosa HOP SEDGE Carex lupulina GREEN BULRUSH Scirpus atrovirens CREEPING SPIKE RUSH Eleocharis palustris SOFT RUSH Juncus effusus FRINGED SEDGE Carex crinita SWAMP MILKWEED Asclepias incarnata Aster puniceus SWAMP ASTER RATTLESNAKE GRASS Glyceria canadensis Mimulus ringens SQUARE STEMMED MONKEY FLOWER SPOTTED JOE PYE WEED Eupatorium maculatum *Iris versicolor* BLUE FLAG

- 100% BIODEGRADABLE EROSION CONTROL BLANKETS MUST BE USED FOR STABILIZATION OF SLOPES IN EXCESS OF 3H:1V AND MAY BE USED IN LIEU OF HYDROSEEDING AT THE CONTRACTOR'S DISCRETION TO PROVIDE ADDITIONAL EROSION PROTECTION
- FINAL STABILIZATION SHALL BE CONSIDERED COMPLETE WHEN ALL SOIL-DISTURBING ACTIVITIES HAVE BEEN COMPLETED AND A UNIFORM, PERENNIAL VEGETATIVE COVER WITH A DENSITY OF EIGHTY PERCENT HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS THE USE OF MULCHES OR EROSION CONTROL MATTING) HAVE BEEN EMPLOYED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL VEGETATED SURFACES, INCLUDING WATERING, FERTILIZING, REPAIRING EROSION, INVASIVE PLANT REMOVAL, AND
- RE-SEEDING UNTIL ESTABLISHMENT CONDITIONS ARE MET AND UNTIL THE END OF THE CONTRACTUAL MAINTENANCE PERIOD. WORK AREA SHALL BE FREE OF INVASIVE PLANT GROWTH AT FINAL COMPLETION AND END OF 1 YEAR WARRANTEE PERIOD.

GENERAL NOTES:

ABBREVIATIONS

BOTTOM OF WALL

EDGE OF WATER

TOP OF WALL

UTILITY POLE

TYPICAL

CORRUGATED METAL PIPE

TEMPORARY BENCHMARK

DIAMETER AT BREAST HEIGHT

ORDINARY HIGH WATER MARK

BOW

BVW

CMP

DBH

EOW

OHW

TBM

TOW

TYP

ELEV,EL ELEVATION

BORDERING LAND SUBJECT TO FLOODING

BORDERING VEGETATED WETLANDS

- 1. THE EXISTING CONDITIONS PLAN IS BASED ON FIELD SURVEY PERFORMED BY BRENNAN CONSULTING IN OCTOBER-NOVEMBER, 2016
- 2. THE HORIZONTAL DATUM SHOWN REFERENCES THE NORTH AMERICAN HORIZONTAL DATUM OF 1983 (NAD83).
- 3. THE VERTICAL DATUM SHOWN REFERENCES THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)
- 4. JURISDICTIONAL WETLAND RESOURCE AREAS WERE DELINEATED BY TIGHE & BOND, IN OCTOBER 2022.
- 5. THE 100-YEAR FLOODING LIMIT WAS ESTABLISHED BASED ON MODELING BY TIGHE & BOND USING SCS TR-55 METHODS AS OUTLINED IN 310 CMR 10.57 (2)(a)(3).

LEGEND

////// DEMOLISH UTILITY POLE MAILBOX OVERHEAD ELECTRIC LINE - PROPOSED CULVERT LINE DRAIN STRUCTURE EDGE OF PAVEMENT ______ GUARDRAIL · OOOOOOOOOOO · STONE WALL · TREE LINE -X X X X X X PROPOSED CHAIN LINK FENCE + BORING — — — — LIMIT OF WORK EROSION AND SEDIMENT CONTROLS STONE MASONRY WALL TREE TO BE REMOVED

PROPOSED RIPRAP

PROPOSED MINOR CONTOUR

— 100 — PROPOSED MAJOR CONTOUR


— — — 100— — MAJOR CONTOUR


MINOR CONTOUR

DBH, AND TYPE

TREE TRUNK LOCATION,

— - - — - - — EDGE OF WATER BORDERING VEGETATED WETLANDS (BVW) ——— - - - — INLAND BANK -----LOCAL RESOURCE AREA BORDERING LAND SUBJECT TO FLOODING — — — 100-FOOT BUFFER ZONE WF—1• WETLAND FLAG . PROPOSED TREE LINE TEST PIT REQUIRED NATIVE STREAMBED MATERIAL





Arnold Pond Dam Removal

Massachusetts Division of Fisheries and Wildlife

Sutton, Massachusetts

1	10/24	Issued For Bidding
MARK	DATE	DESCRIPTION
PROJECT NO:		M944-051
DATE:		10/2024
FILE:	G-002 G	GENERAL NOTES, ABBREVIA
DRAWN BY: CMH,LPT		
DESIGNED/CHECKED BY: DRB,DRH		


GENERAL NOTES, ABBREVIATIONS, AND LEGEND


DRB

NO SCALE SCALE:


PPROVED BY:

G-002 SHEET 2 OF 9






1	10/24	Issued For Bidding
1ARK	DATE	DESCRIPTION
ROJECT NO:		M944-051
ATE:		10/2024
ILE:	C-102 S	SITE PREPARATION AND DE




Tighe&Bond



NOTES

- 1. DEWATERING EQUIPMENT SHALL REMAIN WITHIN THE PERMANENTLY IMPACTED AREAS AND SHALL DISCHARGE OUTSIDE OF THE WETLAND BOUNDARY.
- 2. DISCHARGE HOSE SHALL NOT CROSS THE STREAM AT ANY LOCATION.


COFFERDAM AND DEWATERING NO SCALE



TYPICAL TIMBER MATS IN WETLANDS AREA NO SCALE


NOTES


- 1. TIMBER MATS SHALL BE PLACED CLOSELY TOGETHER SO THERE ARE NO GAPS BETWEEN EACH MAT SECTION
- 2. ADDITIONAL MEASURES MAY BE REQUIRED.
- 3. USE TIMBER MATS FOR TEMPORARY ACCESS, WHERE WORK WILL BE CONTINUOUS, IN WET OR SOFT AREAS.
- 4. BRIDGE EXCESSIVELY WET AREAS WITH MATS.



1. EROSION CONTROL BLANKET SHALL BE 100% BIODEGRADABLE.


- 2. EROSION CONTROL BLANKET SHALL BE INSTALLED VERTICALLY DOWNSLOPE.
- 3. STAKES/STAPLES SHALL BE PLACED NO MORE THAN 3 FT APART VERTICALLY, AND 1 FT APART HORIZONTALLY.
- 4. SLOPE SURFACE SHALL BE FREE OF STICKS, ROCKS, AND OTHER OBSTRUCTIONS.
- 5. BLANKETS SHALL BE ROLLED OUT LOOSELY AND STAKED/STAPLED TO MAINTAIN DIRECT SOIL CONTACT. DO NOT STRETCH THE BLANKETS.





SECTION A-A


SEDIMENT TRAP NO SCALE



SECTION VIEW

NOTES:

- 1. TUBES FOR COMPOST FILTERS SHALL BE JUTE MESH OR APPROVED BIODEGRADABLE MATERIAL. ADDITIONAL TUBES SHALL BE USED AT THE DIRECTION OF THE ENGINEER.
- 2. TAMP TUBES IN PLACE TO ENSURE GOOD CONTACT WITH SOIL SURFACE. IT IS NOT NECESSARY TO TRENCH TUBES INTO EXISTING GRADE.
- 3. WHEN STAKING IS NOT POSSIBLE, SUCH AS WHEN TUBES MUST BE PLACED ON PAVEMENT, HEAVY CONCRETE OR CINDER BLOCKS CAN BE USED BEHIND TUBES UP TO 5' APART OR AS REQUIRED TO SECURE TUBES IN PLACE.



PLAN VIEW - JOIN DETAIL

EROSION CONTROL BARRIER COMPOST FILTER TUBE NO SCALE

NOTES:

- 1. PROVIDE 3' MINIMUM OVERLAP AT ENDS OF TUBES TO JOIN IN A CONTINUOUS BARRIER AND MINIMIZE UNIMPEDED FLOW.
- 2. STAKE JOINING TUBES SNUGLY AGAINST EACH OTHER TO
- PREVENT UNFILTERED FLOW BETWEEN THEM.

 3. SECURE ENDS OF TUBES WITH STAKES SPACED 18" APART THROUGH TOPS OF TUBES.


GENERAL COMPOST FILTER TUBE NOTES:

- 1. PROVIDE A MINIMUM TUBE DIAMETER OF 12" FOR SLOPES UP TO 50' IN LENGTH WITH A SLOPE RATIO OF 3H:1V OR STEEPER. LONGER SLOPES OF 3H:1V MAY REQUIRE LARGER TUBE DIAMETER OR ADDITIONAL COURSING OF FILTER TUBES TO CREATE A FILTER BERM. REFER TO MANUFACTURER'S RECOMMENDATIONS FOR SITUATIONS WITH LONGER SLOPES OR STEEPER SLOPES.
- 2. INSTALL TUBES ALONG CONTOURS AND PERPENDICULAR TO SHEET OR CONCENTRATED FLOW.
- 3. DO NOT INSTALL IN PERENNIAL, EPHEMERAL OR INTERMITTENT STREAMS.
- 4. CONFIGURE TUBES AROUND EXISTING SITE FEATURES TO MINIMIZE SITE DISTURBANCE AND MAXIMIZE CAPTURE AREA OF STORMWATER RUN-OFF.
- 5. TUBES CAN BE PLACED DIRECTLY ON EXISTING PAVEMENT WHEN NECESSARY.
- 6. PLACING TUBES AGAINST THE UPHILL SIDE OF WELL-ANCHORED, STATIONARY
- FEATURES SUCH AS EXISTING TREES, CAN PROVIDE ADDITIONAL BRACING.

 7. CURVE ENDS UPHILL TO PREVENT DIVERSION OF UNFILTERED RUN-OFF.
- 8. STRAW WATTLES WITH A 100% BIODEGRADABLE MESH MAY BE SUBSTITUTED IN AREAS INACESSIBLE FOR FILTER TUBE INSTALLATION EQUIPMENT.

Tighe&Bond





Arnold Pond Dam Removal Project

Massachusetts
Division of
Fisheries and
Wildlife

Sutton, Massachusetts

1	10/24	Issued For Bidding
ARK	DATE	DESCRIPTION
ROJECT NO:		M944-051
ATE:		10/2024
ILE:	C-201 EROSION, SEDIMENT, AND	

DESIGNED/CHECKED BY: DRH,DRB
APPROVED BY: DRB

CMH,LPT


AS SHOWN

DRAWN BY:

EROSION, SEDIMENT, AND WATER CONTROL DETAILS


C 201

C-201



NOTES:
1. REMOVE FOLLOWING CONSTRUCTION.


TEMPORARY CONSTRUCTION ENTRY PAD NO SCALE



REMOVABLE BOLLARD DETAIL


- NOTES:

 1. ALIGN BOLLARD PIPE AND GROUND INSERT SO EYES ARE LOCATED AT BACK AND FRONT OF BOLLARD, NOT PROTRUDING INTO THE TRAVELED
- 2. BOLLARD SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.




COMPACTED FOOT PATH


1. PROVIDE WATER BARS AT INTERVALS IF NECESSARY TO PITCH RUNOFF OFF PATH TO SHEET FLOW ACROSS ADJACENT SURFACE.



COMPACTED STONE SURFACE NO SCALE




PIPE ABANDONMENT NO SCALE



NOTES:

1. SPLIT RAIL FENCE TERMINATION AT 6" BY 6" TIMBER RAIL POSTS IS MORTISED SIMILARLY TO SPLIT RAIL FENCE END POSTS.

SPLIT RAIL FENCE




PLANTING SCHEDULE FOR TOE BUTTRESS

SURFACE TREATMENTS: COVER LIBERALLY WITH EXCAVATED SEDIMENT

SEED: SEED WITH 50% NEW ENGLAND WETLAND MIX AND 50% NEW ENGLAND EROSION CONTROL MIX FOR DRY SITES

PLANTINGS: LIVE STAKES AS RECOMMENDED BY SUPPLIER FOR SEASON, WITHIN COMPACTED SEDIMENT AND COIR LOG AT 4' O.C.; LIVE STAKES TO BE GRIDDED IN CLUSTERS OF 3.

COMMON NAME	BOTANICAL NAME
COMMON WINTERBERRY	Ilex verticillata
BLACK WILLOW	Salix nigra
SILKY DOGWOOD	Swida amomum
WILD RAISIN	Viburnum cassinoides
NORTHERN ARROW-WOOD	Viburnum dentatum




5. PROTECT AND PREVENT UNDERMINING OF EXISTING WALL.

6. USE EXISTING SOIL FOR BACKFILL SUPPLEMENTED WITH GRANULAR FILL.

REBUILT OR NEW DRY STONE

MASONRY WALL - TYPICAL SECTION

Tighe&Bond





Arnold Pond Dam Removal Project

Massachusetts Division of Fisheries and Wildlife


Sutton, Massachusetts


Ţ	10/24	Issued For Bidding	
RK	DATE	DESCRIPTION	
OJECT NO:		M944-051	
TE:		10/2024	
E:	C-202 MISCELLANEOUS DETAILS.d		
AWN BY:		CMH,LPT	
SIGNED/CHECKED BY: DRH,DRB			
PROVED BY:		DRB	

MISCELLANEOUS DETAILS

C-202 SHEET 7 OF 9

AS SHOWN





- 1. DEWATERING IS REQUIRED AT EACH FOUNDATION LOCATION TO CONTROL THE WATER INFLOW AND ADEQUATELY DEWATER THE FOOTING EXCAVATION. SUMP PUMPING AROUND THE ENTIRE PERIMETER MAY BE REQUIRED TO ADEQUATELY CONTROL THE GROUNDWATER WITHIN THE EXCAVATION AREAS. DEWATERING SHALL BE CONTINUOUS UNTIL THE CONCRETE IS BACKFILLED EVENLY ON BOTH SIDES TO THE ELEVATIONS OF THE SURROUNDING WATER TABLE, UNLESS OTHERWISE DIRECTED. ANY PROPOSED DEWATERING SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND ACCEPTANCE.
- 2. WATER PUMPED FROM DEWATERING LOCATIONS SHALL BE FILTERED ADEQUATELY TO REMOVE FINE MATERIALS PRIOR TO RETURNING THE WATER TO THE POND. ACTUAL LOCATION OF SEDIMENTATION BASIN TO BE DETERMINED BY CONTRACTOR AND APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
- 3. ANY FOUNDATION MATERIALS WEAKENED AS A RESULT OF INSUFFICIENT CARE WHILE MAINTAINING A DEWATERED CONDITION SHALL BE REMOVED AND REPLACED WITH GRAVEL BORROW OR CRUSHED STONE AT NO EXPENSE TO THE OWNER. SEE SPECIFICATION SECTION 02320.
- 4. THE CONTRACTOR SHALL SUBMIT DRAWINGS AND DESIGN CALCULATIONS, SEALED AND SIGNED BY A CURRENTLY REGISTERED MASSACHUSETTS PROFESSIONAL ENGINEER TO THE ENGINEER FOR REVIEW AND ACCEPTANCE OF THE PROPOSED SHORING AND SUPPORT OF EXCAVATION. SHOP DRAWINGS AND CALCULATIONS SHALL BE SUBMITTED PRIOR TO FABRICATION AND INSTALLATION FOR ALL SHORING AND SUPPORT OF EXCAVATION ELEMENTS.

Tighe&Bond





Arnold Pond Dam Removal Project

Massachusetts
Division of
Fisheries and
Wildlife

Sutton, Massachusetts

1	9/24	Issued For Bidding	
MARK	DATE	DESCRIPTION	
PROJECT NO: M944-051			
DATE:	9/2024		
FILE:	S-201 PEDESTRIAN BRIDGE PLAN		
DRAWN BY: AvC			
DESIGNED/CHECKED BY: AvC, DH			

PEDESTRIAN BRIDGE AND

ABUTMENT DETAILS

SCALE: AS SHOWN

SCALE: 3/8"=1'-0"

S-201SHEET 9 OF 9

GENERAL

- 1. STRUCTURAL WORK SHALL CONFORM TO STATE BUILDING CODE, LATEST EDITION, INCLUDING MOST RECENT ADDENDA, AND CONTRACT DOCUMENTS. IN CASE OF CONFLICT, MOST STRINGENT REQUIREMENT SHALL GOVERN. DESIGN OF BRIDGE SHALL BE GOVERNED BY AASHTO LRFD GUIDE SPECIFICATIONS FOR THE DESIGN OF PEDESTRIAN BRIDGES, LATEST EDITION WITH INTERIM REVISIONS.
- 2. CONTRACTOR SHALL VERIFY AND COORDINATE DIMENSIONS RELATED TO THIS PROJECT.
- 3. CONTRACTOR SHALL EXAMINE DRAWINGS FOR ALL TRADES FOR THE VERIFICATION OF LOCATION AND DIMENSIONS OF ALL PROJECT REQUIREMENTS NOT SHOWN ON THE STRUCTURAL DRAWINGS.

REINFORCEMENT

- 1. DETAILING, FABRICATION, AND ERECTION OF REINFORCEMENT, UNLESS OTHERWISE NOTED, SHALL CONFORM TO ACI "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE (ACI 318)" AND ACI "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES (ACI 315)", LATEST EDITION.
- 2. STEEL REINFORCEMENT UNLESS OTHERWISE SHOWN SHALL CONFORM TO ASTM A615 GRADE 60 MINIMUM (YIELD STRENGTH - 60,000 PSI).
- 3. PROVIDE AND SCHEDULE ON SHOP DRAWINGS, ALL NECESSARY ACCESSORIES TO HOLD REINFORCEMENT SECURELY IN POSITION: MINIMUM REQUIREMENTS SHALL BE: HIGH CHAIRS, 4'-0" ON CENTER, #5 SUPPORT BAR FOR HIGH CHAIRS, SLAB BOLSTERS, 3'-6" ON CENTER, ALL WIRE CHAIRS AND BOLSTERS TO BE PLASTIC TIPPED.
- 4. THE CONCRETE PROTECTIVE COVERING FOR REINFORCEMENT SHALL BE AS SHOWN ON THESE DRAWINGS AND NO LESS THAN 2" AGAINST FORMS, OR 3" AGAINST EARTH.
- WHERE REINFORCEMENT IS NOT SHOWN ON DRAWINGS, PROVIDE REINFORCEMENT IN ACCORDANCE WITH APPLICABLE TYPICAL DETAILS OR AS SHOWN FOR MOST SIMILAR DETAIL, AS DETERMINED BY THE ENGINEER. IN NO CASE SHALL REINFORCEMENT BE LESS THAN MINIMUM REINFORCEMENT PERMITTED BY THE APPLICABLE CODES, NOR LESS THAN THE FOLLOWING:
- A. STRUCTURAL FOOTINGS .0028 GROSS CONCRETE AREA IN EACH DIRECTION
- B. STRUCTURAL WALLS .0028 GROSS CONCRETE AREA IN EACH DIRECTION
- WHERE REINFORCEMENT IS CALLED FOR IN SECTION, REINFORCEMENT IS CONSIDERED TYPICAL WHEREVER THE SECTION APPLIES.
- 7. REINFORCEMENT SHALL BE CONTINUOUS THROUGH ALL CONSTRUCTION JOINTS UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- 8. REINFORCEMENT COUPLER SPLICES SHALL BE MECHANICAL DEVICES CAPABLE OF TRANSMITTING THE ULTIMATE TENSILE AND COMPRESSIVE STRENGTH OF THE BAR.
- 9. INSTALLATION OF REINFORCEMENT SHALL BE COMPLETE AT LEAST 24 HOURS PRIOR TO SCHEDULED CONCRETE PLACEMENT. NOTIFY ENGINEER OF COMPLETION AT LEAST 24 HOURS PRIOR TO SCHEDULED COMPLETION OF REINFORCEMENT PLACEMENT.
- 10. REINFORCEMENT SHALL BE SET BEFORE PLACING CONCRETE. SETTING ANY REINFORCEMENT INTO WET CONCRETE IS PROHIBITED.

CONCRETE


- 1. CONCRETE WORK SHALL CONFORM TO THE LATEST EDITIONS OF THE BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE (ACI 318), AND SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDING (ACI 301).
- 2. CONCRETE SHALL BE CONTROLLED CONCRETE, PROPORTIONED, MIXED, AND PLACED UNDER THE SUPERVISION OF AN APPROVED CONCRETE TESTING AGENCY OR THE ENGINEER.
- 3. CONCRETE SHALL BE NORMAL WEIGHT CONCRETE AND SHALL HAVE A COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS, AND A MAXIMUM WATER TO CEMENT RATIO NOT GREATER THAN 0.45 UNLESS OTHERWISE NOTED AND SHALL BE AIR ENTRAINED. SEE SPECIFICATION 03300.
- 4. WHERE CONSTRUCTION JOINTS ARE NOT SHOWN BUT PROPOSED BY THE CONTRACTOR, DRAWINGS SHOWING LOCATION OF CONSTRUCTION JOINTS AND CONCRETE PLACING SEQUENCE SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO PREPARATION OF THE REINFORCEMENT SHOP DRAWINGS.
- 5. CONCRETE SHALL BE PLACED WITHOUT HORIZONTAL CONSTRUCTION JOINTS EXCEPT WHERE SHOWN OR NOTED.
- 6. EXPOSED EDGES OF CONCRETE ELEMENTS SHALL HAVE CHAMFERED CORNERS


FOUNDATIONS

- 1. NO CONCRETE SHALL BE PLACED IN WATER OR ON FROZEN GROUND.
- 2. BOTTOM OF FOUNDATION ELEVATIONS GIVEN ON DRAWINGS ARE TO BE CONSIDERED MINIMUM DEPTHS. CONTRACTOR SHALL HAVE FURTHER EXCAVATION AS REQUIRED TO REACH ADEQUATE BEARING.
- 3. ALL EXCAVATIONS FOR FOOTINGS SHALL BE FINISHED BY HAND FOR THE LAST 6".
- 4. ALL FINISHED EXCAVATIONS SHALL BE INSPECTED BY THE ENGINEER BEFORE ANY CONCRETE IS PLACED.
- 5. ALL BACKFILL UNDER OR ADJACENT TO ANY PORTION OF THE STRUCTURES SHALL BE COMPACTED IN 6" LIFTS. SEE SPECIFICATIONS.
- REMOVE UNSUITABLE FILL AND/OR IMPROVE THE SUBGRADE PER SPECIFICATION REQUIREMENTS. BACKFILL WITH COMPACTED STRUCTURAL (GRANULAR) FILL UP TO THE UNDERSIDE OF THE PROPOSED CRUSHED STONE LAYER. SEE SPECIFICATION SECTION 02315.
- 7. ANY UNSUITABLE MATERIAL SUCH AS BOULDERS, EXISTING SUBSTRUCTURES, ROOTS, ORGANIC SOILS, OR SILT/CLAY ENCOUNTERED WITHIN THE FOUNDATION BEARING ZONE, DEFINED BY A 1H:1V PLANE EXTENDING DOWNWARD AND OUTWARD FROM 1 FOOT BEYOND THE EDGE OF FOOTING, SHALL BE REMOVED AND REPLACED WITH CRUSHED STONE, AS DIRECTED BY THE ENGINEER.


REBAR SPLICE LENGTH NOTES

- 1. IF CLEAR SPACING BETWEEN THE REBARS IS LESS THAN THREE BAR DIAMETERS, OR IF COVER IS LESS THAN TWO BAR DIAMETERS, INCREASE THE SPLICE LENGTH BY AN ADDITIONAL 50%.
- 2. IF LIGHTWEIGHT CONCRETE IS USED, INCREASE THE SPLICE LENGTH BY AN ADDITIONAL 30%.
- 3. THE MINIMUM REBAR SPLICE LENGTH SCHEDULE IS BASED ON F'c= 4,000 PSI AND Fy= 60,000 PSI. ADJUST FOR OTHER STRENGTHS USING ACI-318.
- 4. FOR HORIZONTAL REINFORCEMENT SO PLACED THAT MORE THAN 12 INCHES OF FRESH CONCRETE IS CAST IN THE MEMBER BELOW, INCREASE THE DEVELOPMENT LENGTH BY AN ADDITIONAL 30%.
- WHEN BARS OF DIFFERENT SIZE ARE LAP SPLICED, THE SPLICE LENGTH SHALL BE THE LARGER OF EITHER THE DEVELOPMENT LENGTH OF THE LARGER BAR OR THE SPLICE LENGTH OF THE SMALLER BAR.






REBAR SPLICE LENGTH SCHEDULE



REINFORCEMENT PLAN AT CHEEK WALL




BEARING (TYP) -

- 4"Ø WEEP HOLE

ABUTMENT PLAN

-11'-0" BRIDGE SEAT (ASSUMED, SEE NOTE 2)-





FOOTING HEEL

- FOOTING TOE


∠ 2" CHAMFER (TYP)

SCALE: 3/4"=1'-0"


Arnold Pond Dam Removal **Project**

Massachusetts Division of Fisheries and Wildlife

Sutton, Massachusetts




SHEET 9 OF 9



1. SETTING PLATE, ELASTOMERIC PAD, BEARING PLATE, AND ANCHOR BOLTS FURNISHED BY PEDESTRIAN BRIDGE MANUFACTURER.

BEARING DETAIL



1. ADJUST DIMENSIONS TO ACCOMMODATE MANUFACTURER SYSTEM

NOTES: 1. ONE ABUTMENT SHOWN, OTHER SIMILAR.

10" BACKWALL -

1'-2" BRIDGE SEAT -

- BEARING (TYP)

2. COORDINATE BRIDGE SEAT DIMENSIONS WITH BRIDGE MANUFACTURER. NOTIFY ENGINEER IF THIS DIMENSION NEEDS TO VARY FROM WHAT IS SHOWN IN ORDER TO ACCOMMODATE THE BRIDGE.


ABUTMENT ELEVATION

3. WEEP HOLE TO BE LOCATED APPROXIMATELY 12" ABOVE NORMAL POOL ELEVATION. COORDINATE EXACT LOCATION WITH STEM REINFORCING.

MASSACHUSETTS DIVISION OF FISHERIES AND WILDLIFE SALMON BROOK DAM REMOVAL PROJECT


BROOKFIELD, MASSACHUSETTS OCTOBER 2024

LIST OF DRAWINGS		
SHEET NO.	DRAWING NO.	DRAWING TITLE
GENERAL		
1	G-001	COVER SHEET
2	G-002	GENERAL NOTES, ABBREVIATIONS, AND LEGEND
CIVIL		
3	C-101	EXISTING CONDITIONS PLAN
4	C-102	CONSTRUCTION ACCESS, SITE PREPARATION, AND DEMOLITION PLAN
5	C-103	PROPOSED CONDITIONS AND SITE RESTORATION PLAN
6	C-104	CULVERT REMOVAL PLAN
7	C-201	EROSION, SEDIMENT, AND WATER CONTROL DETAILS



PREPARED BY:

Tighe&Bond





PREPARED FOR:

MASSACHUSETTS DIVISION OF FISHERIES AND WILDLIFE

CALEB SLATER, PhD, CHIEF OF HATCHERIES

1: 10/3/2024 :Oct 03, 2024-1:19pm By: DHammerberg

EROSION AND SEDIMENTATION CONTROL NOTES:

COMPLETION OF CLEARING AND GRUBBING BUT PRIOR TO COMMENCEMENT OF GRADING ACTIVITIES.

- TEMPORARY SEDIMENT AND EROSION CONTROL BY THE CONTRACTOR SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATIONS LISTED BELOW
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING ALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES NECESSARY TO EXECUTE AND COMPLETE THE WORK OF THE CONTRACT, IN COMPLIANCE WITH THE TERMS AND CONDITIONS CONTAINED IN THE CONTRACT AND PROJECT PERMITS. CONTROLS SHOWN ON THE CONTRACT DRAWINGS AND MENTIONED IN THE TECHNICAL SPECIFICATIONS SHALL BE CONSIDERED MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL EMPLOY WHATEVER SUPPLEMENTARY MEASURES NECESSARY TO PROTECT WETLANDS, WATERS, AND ADJACENT AREAS FROM DISTURBANCE OR DISCHARGE OF SEDIMENTS
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SEDIMENT AND EROSION CONTROLS TO MEET THE CONDITIONS OF ALL APPLICABLE PERMITS AND REGULATIONS. SUCH CONTROLS SHALL BE INSTALLED WHEREVER THE POTENTIAL EXISTS FOR THE DISTURBANCE OF LAND OR THE TRANSPORT OF SEDIMENT.
- EROSION AND SEDIMENTATION PERIMETER CONTROLS SHALL CONSIST OF 100% BIODEGRADABLE COMPOST FILTER TUBES INSTALLED PER DETAILS PROVIDED ON SHEET C-201. PLASTIC MESH MATERIALS SHALL NOT BE PERMITTED
- COMPOST FILTER TUBES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF CLEARING AND GRUBBING ACTIVITIES. LOCATION OF COMPOST FILTER TUBES TO BE ADJUSTED UPON
- ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE MAINTAINED IN GOOD CONDITION AND PROPER WORKING ORDER. NECESSARY REPAIRS SHALL BE MADE IMMEDIATELY.
- ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE PROPERLY DISPOSED OFF-SITE UPON COMPLETION OF WORK, SITE STABILIZATION AND/OR AUTHORIZATION FROM THE E7. OWNER
- MAINTAIN AN ADDITIONAL SUPPLY OF EROSION CONTROL MEASURES ONSITE THROUGHOUT THE CONSTRUCTION PERIOD.
- SILT TRAPPED AT BARRIERS SHALL BE REMOVED AND DISPOSED OF IN UPLAND AREAS OUTSIDE BUFFER ZONES. MATERIALS DEPOSITED IN ANY TEMPORARY SETTLING BASIN SHALL BE REMOVED AT THE COMPLETION OF THE PROJECT. ALL DISTURBED AREAS SHALL BE RESTORED.
- E10. INSTALL EROSION CONTROLS AT THE EDGE OF PROPOSED WORK. EROSION CONTROLS SHALL ACT AS LIMIT OF WORK LINE TO HELP ENSURE THAT EQUIPMENT DOES NOT DISTURB ADJACENT PROPERTIES.
- E11. ADDITIONAL EROSION CONTROLS MAY BE REQUIRED TO PREVENT SEDIMENTS FROM DISCHARGING TO ADJACENT PROPERTIES OR INTO EXISTING STORM DRAIN SYSTEMS.
- E12. STABILIZE THE AREAS OF CONSTRUCTION ACTIVITIES AT THE CLOSE OF EACH CONSTRUCTION DAY. CHECK EROSION CONTROLS AT THIS TIME AND MAINTAIN OR REINFORCE IF NECESSARY.
- PROTECT NEW WORK FROM FLOODING. PROPERLY SLOPE GRADING IN THE AREAS SURROUNDING ALL EXCAVATIONS TO PREVENT WATER FROM RUNNING INTO THE EXCAVATED AREA OR TO ADJACENT PROPERTIES. UPON COMPLETION OF THE WORK, RESTORE ALL AREAS IN A SATISFACTORY MANNER DETERMINED BY THE OWNER.
- E14. ALL SILT-LADEN WATER MUST BE SETTLED OR FILTERED TO REMOVE ALL SEDIMENTS IN A SEDIMENTATION BASIN OR FILTER BAG LOCATED DOWNSTREAM, PRIOR TO RELEASE
- TO A WATERWAY OR EXISTING DRAINAGE SYSTEM. E15. DEWATER AS NECESSARY TO KEEP CONSTRUCTION AREAS FREE OF WATER, DISCHARGE WATER FROM DEWATERING TO THE APPROPRIATE LOCATION AND WITHOUT SEDIMENT.
- E16. AT THE END OF EACH WORK DAY, ANY SEDIMENTS TRACKED ONTO PUBLIC RIGHT-OF-WAYS BEYOND THE PROJECT LIMITS SHALL BE SWEPT AWAY

BEST MANAGEMENT PRACTICES

INSPECTION AND MAINTENANCE

- SEDIMENT, EROSION CONTROLS, AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE INSTALLED PRIOR TO COMMENCING CONSTRUCTION AT THE SITE. NO WORK WHICH SHALL DISTURB THE SITE OR CREATE THE POTENTIAL FOR SEDIMENT RELEASE SHALL COMMENCE UNTIL THE SEDIMENT AND EROSION CONTROLS HAVE BEEN INSPECTED AND APPROVED BY THE OWNER, ENGINEER, AND REGULATORY AGENCIES. ALL CONTROLS AND BMPS SHALL BE SUBJECT TO INSPECTION BY THE OWNER, THEIR REPRESENTATIVE, AND REGULATORY AGENCIES AT ANYTIME THEREAFTER.
- PERIODIC INSPECTION, MAINTENANCE, AND CLEANING OF TEMPORARY EROSION OF SEDIMENT CONTROL MEASURES AND BEST MANAGEMENT PRACTICES (BMPS) SHALL BE REQUIRED. ALL CONTROLS AND BMPS SHALL BE INSPECTED EVERY 7 DAYS AND WITHIN 24 HOURS OF RAINFALL EVENTS OF 0.5 INCHES OR GREATER. ROUTINE INSPECTION AND MAINTENANCE WILL REDUCE THE CHANCE OF POLLUTING STORMWATER BY FINDING AND CORRECTING PROBLEMS BEFORE THE NEXT RAIN EVENT. THE FOCUS OF THE INSPECTION WILL BE TO DETERMINE:
 - . WHETHER OR NOT THE MEASURE WAS INSTALLED / PERFORMED CORRECTLY;
 - . WHETHER OR NOT THERE HAS BEEN ANY DAMAGE TO THE MEASURE SINCE IT WAS INSTALLED OR PERFORMED; AND
- 3. WHAT SHOULD BE DONE TO CORRECT ANY PROBLEMS WITH THE MEASURE. EACH MEASURE IS TO BE OBSERVED TO DETERMINE IF IT IS STILL EFFECTIVE. IN SOME CASES, SPECIFIC MEASUREMENTS MAY BE TAKEN TO DETERMINE IF MAINTENANCE OF THE MEASURES IS REQUIRED.

• PRIOR TO CONSTRUCTION, A SITE MANAGER WILL BE DESIGNATED BY THE CONTRACTOR TO BE RESPONSIBLE FOR INSTALLATION, MONITORING, INSPECTION, AND CORRECTION OF EROSION AND SEDIMENT CONTROL MEASURES.

SITE CLEARING

DURING SITE CLEARING, EXISTING VEGETATION WITHIN THE OVERALL LIMITS OF CLEARING AND GRUBBING SHALL BE REMOVED, EXCEPT AS OTHERWISE DIRECTED. PRIOR TO ANY SITE CLEARING ACTIVITIES, SEDIMENT CONTROL BARRIERS SHALL BE PLACED ALONG THE OUTER LIMIT OF DISTURBANCE. CLEARING IS TO BE LIMITED TO THOSE AREAS OF PROPOSED WORK. DISTURBED AREAS ARE TO BE KEPT TO A MINIMUM. NO VEGETATION SHALL BE CLEARED FROM AREAS OUTSIDE THE LIMITS OF CLEARING AND GRUBBING

EROSION CONTROL BARRIERS

WITHOUT PRIOR APPROVAL FROM THE OWNER.

• COMPOST FILTER TUBE BARRIERS ARE TO BE PLACED TO TRAP SEDIMENT TRANSPORTED BY RUNOFF BEFORE IT REACHES THE DRAINAGE FEATURES, WATERBODIES, OR WETLANDS, IN ADDITION TO AREAS WHERE HIGH RUNOFF VELOCITIES OR HIGH SEDIMENT LOADS ARE EXPECTED. THE COMPOST FILTER TUBES ARE TO BE REPLACED AS DETERMINED BY PERIODIC FIELD INSPECTIONS.

• STANDARD DUST CONTROL MEASURES, INCLUDING SPRAYING AND MISTING SHALL BE USED AS NECESSARY. CALCIUM CHLORIDE SHALL NOT BE ALLOWED ON THIS PROJECT.

- THE CONTRACTOR SHALL COORDINATE LAYDOWN STAGING AREAS IN WHICH TO STORE EQUIPMENT AND MATERIALS WITH THE OWNER.
- STAGING AREAS SHALL BE SURROUNDED WITH COMPOST FILTER TUBE EROSION BARRIERS ON THE DOWNHILL SIDE.
- DURING AND AFTER CONSTRUCTION, ALL PAVED ROAD AND DRIVEWAY SURFACES ARE TO BE SCRAPED AND BROOMED FREE OF EXCAVATED MATERIALS ON A DAILY BASIS, UNLESS APPROVED BY THE OWNER.

STOCKPILED MATERIALS

- STOCKPILES OF SOIL CREATED DURING CONSTRUCTION ACTIVITIES ARE TO BE SURROUNDED WITH AN EROSION CONTROL BARRIER AROUND THE PERIMETER OF THE STOCKPILE. STOCKPILES OF ERODIBLE MATERIAL ARE TO BE COVERED PRIOR TO INCLEMENT WEATHER WITH A MINIMUM OF 20 MIL POLYETHYLENE SHEETING. STOCKPILES LEFT UNDISTURBED LONGER THAN 14 DAYS SHALL BE SEEDED OR COVERED.
- STOCKPILES OF MATERIALS FOR SPECIAL DISPOSAL SHALL ALSO BE UNDERLAID WITH 20 MIL (MIN) POLYETHYLENE SHEETING.

 EQUIPMENT FUELING AND OTHER ACTIVITIES INVOLVING PETROLEUM, OIL, OR OTHER POTENTIALLY HAZARDOUS SUBSTANCES ARE TO BE PERFORMED AT PRE-APPROVED, DESIGNATED AREAS WITH APPROPRIATE SPILL PREVENTION AND CONTROL MEASURES. PORTABLE SECONDARY CONTAINMENT IS TO BE USED, AND SORBENT MATERIALS ARE TO BE PLACED AROUND THE PERIMETER OF THE FUELING AREA

CONSTRUCTION DEWATERING

- CONSTRUCTION DEWATERING SHALL BE REQUIRED DURING PORTIONS OF CONSTRUCTION WHICH REQUIRE EXCAVATION OR OTHER ACTIVITIES WHERE GROUNDWATER MAY
- INTERFERE WITH THE WORK. • CONSTRUCTION DEWATERING DISCHARGE TO A SURFACE WATER BODY SHALL BE PRE-TREATED FOR SEDIMENT REMOVAL BY PASSING THROUGH AN APPROPRIATELY SIZED FILTER
- SOCK, SILT BAG, FRACTIONATION / SEDIMENTATION TANK, OR SEDIMENT TRAP PRIOR TO DISCHARGE, AS NECESSARY. • THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING DEWATERING TECHNIQUES AND MAINTAINING DEWATERING PROCEDURES THROUGHOUT THE DURATION OF THE PROJECT.

• APPROPRIATE OUTLET PROTECTION, CONSISTING OF RIPRAP CHANNEL LINING, A LEVEL SPREADER, OR OTHER SUCH MEASURE SHALL BE PROVIDED AT THE OUTLET OF ANY DEWATERING CONDUIT OR STORMWATER CULVERT OR CHANNEL OUTFALL TO REDUCE VELOCITIES AND ENHANCE SEDIMENTATION PRIOR TO DISCHARGE.

• THE CONTRACTOR SHALL LINE THE UPGRADIENT BOUNDARY OF WORK AREAS WITH ORANGE SAFETY FENCING BEFORE THE START OF SITE CLEARING ACTIVITIES.

 THE CONTRACTOR MUST MAINTAIN THE FLOWAGE OF SURFACE WATER THROUGH THE WORK AREA IN ACCORDANCE WITH THE SPECIFICATIONS. ALL COFFERDAMS SHALL CONSIST OF NON-ERODIBLE MATERIAL HOWEVER WORK MAY BE DONE IN THE WET. THE CONTRACTOR SHALL SUBMIT A WATER CONTROL PLAN THAT WILL ADDRESS PROCEDURES THAT WILL WILL BE USED IN A CONTROLLED MANNER AND EMERGENCY MEASURES TO IMPLEMENT IN THE EVENT A STORM OCCURS DURING CONSTRUCTION.

TEMPORARY STABILIZATION

- WHEN NECESSARY, TEMPORARY SLOPE PROTECTION SHALL BE PROVIDED BY INSTALLING SEDIMENT TRAP BARRIERS AT THE TOE OF FILLS OR CUT SLOPES. IF ADDITIONAL STABILIZATION IS NEEDED, THEN THE CONTRACTOR SHALL INSTALL MULCH LOGS, MATTING, SUCH AS STRAW, JUTE, WOOD FIBER, OR BIODEGRADABLE MESH. A TACKIFIER SHALL BE USED ON LOOSE MATERIALS USED FOR TEMPORARY EROSION CONTROL
- IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN TWO WEEKS, THE AREAS SHALL BE MULCHED WITH STRAW AT A RATE OF 100 LBS. PER 1,000 S.F. TO HELP CONTROL EROSION. 100% BIODEGRADABLE EROSION CONTROL BLANKETS OR TWO INCHES OF WOOD CHIP MULCH MAY ALSO BE USED AS TEMPORARY COVER.
- IN THE EVENT THAT DISTURBED AREAS AT THE SITE ARE TO BE LEFT UN-WORKED FOR MORE THAN ONE MONTH, THE AREAS SHALL BE TOPSOILED AND SEEDED AS PER THE SPECIFICATIONS AND AT NO ADDITIONAL COST TO THE OWNER.
- LEAVE THE SURFACE OF ALL EXCAVATIONS AND FILLS IN A FIRM AND STABLE CONDITION AT THE END OF EACH DAY. ROLL OR OTHERWISE TREAT THE SURFACE AS NEEDED.

- STABILIZATION OF DISTURBED AREAS OR NEW SOIL FILLS SHALL BE IMPLEMENTED WITHIN 14 DAYS AFTER GRADING OR CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED APPROPRIATE VEGETATIVE SOIL STABILIZATION IS TO BE USED TO MINIMIZE EROSION. TEMPORARY AND PERMANENT VEGETATIVE COVER IS TO BE ESTABLISHED IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF PREVIOUSLY VEGETATED UPLAND AREAS DISTURBED BY CONSTRUCTION ACTIVITIES. RESTORATION OF UPLAND AREAS CONSIST OF REPLACEMENT OF TOPSOIL OR PLACEMENT OF IMPORTED LOAM AS NEEDED SUCH THAT A MINIMUM OF 4 INCHES OF SUITABLE MATERIAL IS PRESENT AND APPROPRIATELY LIMED, FERTILIZED, GRADED, AND SCARIFIED. FIELDS DISTURBED OR COMPACTED BY CONSTRUCTION ACTIVITIES SHALL BE PLOWED TO LOOSEN THE SOIL, HARROWED TO PROVIDE AN EVEN SURFACE, AND APPROPRIATELY PREPARED FOR PLANTING.
- DISTURBED UPLAND AREAS SHALL THEN BE HYDROSEEDED WITH AN APPROVED SEED MIX AT THE RATE RECOMMENDED BY THE MANUFACTURER. SEEDING RATE SHALL BE DOUBLED FOR
- DORMANT SEEDING. SEED MIX SHALL BE THE FOLLOWING UNLESS OTHERWISE NOTED OR AS APPROVED BY THE ENGINEER. NATIVE TREE PLANTINGS TO CONSIST OF 4 VARIETIES MIN., WHITE PINE, HEMLOCK, RED MAPLE, BEECH OAK, ACCEPTABLE.

THE NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DRY SITES:

<u>BOTANICAL NAME</u> CREEPING RED FESCUE Festuca rubra Elumus canadensis CANADA WILD RYE $Lolium\ multiflorum$ ANNUAL RYEGRASS Lolium perenne PERENNIAL RYEGRASS Bouteloua gracilis BLUE GRAMA Schizachyrium scoparium LITTLE BLUESTEM Sorghastrum nutans INDIAN GRASS ROUGH BENTGRASS/TICKLEGRASS Agrostis scabia Agrostis perennans **UPLAND BENTGRASS**

DAMP, WET, OR WETLAND ARES:

THE NEW ENGLAND WETLAND SEED MIX:

BOTANICAL NAME FOX SEDGE Carex vulpinoidea **BLUNT BROOM SEDGE** Carex scoparia Verbena hastata BLUE VERVAIN Carex lurida LURID SEDGE FOWL BLUEGRASS Poa palustris Bidens aristosa TICKSEED SUNFLOWER/BUR MARIGOLD Carex lupulina HOP SEDGE Scirpus atrovirens GREEN BULRUSH Eleocharis palustris CREEPING SPIKE RUSH Juncus effusus SOFT RUSH Carex crinita FRINGED SEDGE SWAMP MILKWEED Asclepias incarnata SWAMP ASTER Aster puniceus RATTLESNAKE GRASS Glyceria canadensis Mimulus ringens SQUARE STEMMED MONKEY FLOWER Eupatorium maculatum SPOTTED JOE PYE WEED

BLUE FLAG

- 100% BIODEGRADABLE EROSION CONTROL BLANKETS MUST BE USED FOR STABILIZATION OF SLOPES IN EXCESS OF 3H:1V AND MAY BE USED IN LIEU OF HYDROSEEDING AT THE CONTRACTOR'S DISCRETION TO PROVIDE ADDITIONAL EROSION PROTECTION
- FINAL STABILIZATION SHALL BE CONSIDERED COMPLETE WHEN ALL SOIL-DISTURBING ACTIVITIES HAVE BEEN COMPLETED AND A UNIFORM, PERENNIAL VEGETATIVE COVER WITH A DENSITY OF EIGHTY PERCENT HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS THE USE OF MULCHES OR EROSION CONTROL MATTING) HAVE BEEN EMPLOYED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL VEGETATED SURFACES, INCLUDING WATERING, FERTILIZING, REPAIRING EROSION, INVASIVE PLANT REMOVAL, AND
- RE-SEEDING UNTIL ESTABLISHMENT CONDITIONS ARE MET AND UNTIL THE END OF THE CONTRACTUAL MAINTENANCE PERIOD. WORK AREA SHALL BE FREE OF INVASIVE PLANT GROWTH AT FINAL COMPLETION AND END OF 1 YEAR WARRANTEE PERIOD.

GENERAL NOTES:

- 1. THE EXISTING CONDITIONS PLAN IS BASED ON LIGHT DETECTION AND RANGING (LIDAR) TERRAIN AND ELEVATION DATA COLLECTED FROM 2013 TO 2014 BY THE U.S. GEOLOGICAL SURVEY, AND SITE VISITS.
- 2. THE HORIZONTAL DATUM SHOWN REFERENCES THE NORTH AMERICAN HORIZONTAL DATUM OF 1983 (NAD83).

Iris versicolor

- 3. THE VERTICAL DATUM SHOWN REFERENCES THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88).
- 4. WETLAND RESOURCE AREAS SUBJECT TO LOCAL AND STATE JURISDICTION, ALONG WITH WATERS OF THE UNITED STATES (WOTUS) WERE DELINEATED BY TIGHE & BOND, IN
- 5. THE 100-YEAR FLOODING LIMIT WAS ESTABLISHED BASED ON MODELING BY TIGHE & BOND USING SCS TR-55 METHODS AS OUTLINED IN 310 CMR 10.57 (2)(a)(3).

ABBREVIATIONS

CORRUGATED METAL PIPE DIAMETER AT BREAST HEIGHT ELEV,EL ELEVATION EDGE OF WATER ORDINARY HIGH WATER MARK

TEMPORARY BENCHMARK TOW TOP OF WALL BOW BOTTOM OF WALL TYP TYPICAL UTILITY POLE VEGETATED WETLAND

LEGEND

REMOVE OR DEMOLISH UTILITY POLE SIGN MAILBOX - OVERHEAD ELECTRIC LINE PROPOSED CULVERT LINE DRAIN STRUCTURE — - - — - - — PROPERTY LINE — - - — - - — TOWN LINE EDGE OF PAVEMENT EXISTING GUARDRAIL TREE LINE -x x x x x x PROPOSED CHAIN LINK FENCE BORING — — — — LIMIT OF WORK •••••••EROSION AND SEDIMENT CONTROLS OOOOOOOOCOFFERDAM STONE MASONRY WALL TREE TO BE REMOVED PROPOSED RIPRAP

— — — — 101 — — — EXISTING MINOR CONTOUR


- PROPOSED MAJOR CONTOUR TREE TRUNK LOCATION,


DBH, AND TYPE

— — — 100— — EXISTING MAJOR CONTOUR

— - - — - - — 200-FOOT RIVERFRONT AREA BORDERING VEGETATED WETLANDS ——— – – – — INLAND BANK ----- BORDERING LAND SUBJECT TO FLOODING (BLSF) — — — — — 100-FOOT BUFFER ZONE WF—1 • WETLAND FLAG . PROPOSED TREE LINE TEST PIT REQUIRED NATIVE STREAMBED MATERIAL - TOP OF SEDIMENT CONTOUR — — — — — — BOTTOM OF SEDIMENT CONTOUR

— — — — — — — POSSIBLE CHANNEL CONTOUR





Salmon Brook **Dam Removal**

Massachusetts Division of Fisheries and Wildlife

Brookfield, Massachusetts

1	9/24	Issued For Bidding
MARK	DATE	DESCRIPTION
PROJECT NO:		M0944-051
DATE:		9/2024
FILE:		GENERAL NOTES.dwg
DRAWN BY:		CMH/ARG


GENERAL NOTES, ABBREVIATIONS, AND LEGEND


CDH


SCALE: NO SCALE

DESIGNED/CHECKED BY: DRB/DRH

G-002 SHEET 2 OF 7












PHOTO NO. 1 EXISTING STONE WALL TO BE PROTECTED AND TO REMAIN INTACT



<u>PHOTO NO. 2</u> CULVERT TO BE REMOVED



PHOTO NO. 3 CULVERT TO BE REMOVED



STREAMBED RESTORATION PLAN NO SCALE





PHOTO LOCATION PLAN 1"=40'



LEGEND

9/2024 FILE: C-103 PROPOSED CONDITIONS.dwg CMH DESIGNED/CHECKED BY: DRB

CULVERT REMOVAL PLAN

9/24 Issued For Bidding

MARK DATE DESCRIPTION


PROJECT NO:

DRAWN BY:

APPROVED BY:

AS SHOWN

C-104




Salmon Brook Dam Removal Project

SCALE: 1" = 20'

Tighe&Bond

Massachusetts Division of Fisheries and Wildlife


Brookfield, Massachusetts



NOTES

- 1. DEWATERING EQUIPMENT SHALL REMAIN WITHIN THE PERMANENTLY IMPACTED AREAS AND SHALL DISCHARGE OUTSIDE OF THE WETLAND BOUNDARY.
- 2. DISCHARGE HOSE SHALL NOT CROSS THE STREAM AT ANY LOCATION.


COFFERDAM AND DEWATERING NO SCALE



TYPICAL TIMBER MATS IN WETLANDS AREA NO SCALE

NOTES

- 1. TIMBER MATS SHALL BE PLACED CLOSELY TOGETHER SO THERE ARE NO GAPS BETWEEN EACH MAT SECTION.
- 2. ADDITIONAL MEASURES MAY BE REQUIRED.
- 3. USE TIMBER MATS FOR TEMPORARY ACCESS, WHERE WORK WILL BE CONTINUOUS, IN WET OR SOFT AREAS.
- 4. BRIDGE EXCESSIVELY WET AREAS WITH MATS.



NO SCALE

1. EROSION CONTROL BLANKET SHALL BE 100% BIODEGRADABLE.

GROUND SLOPE

PUMP DISCHARGE

WITH SEDIMENT LADEN WATER

DISCHARGE -

FILTER BAG, CAPACITY OF FILTER

BAG SHALL BE ADEQUATE TO

HANDLE DEWATERING PUMP

FILTER FABRIC MAT OVERLAID


SEDIMENT-

6" CRUSHED STONE

WITH CRUSHED STONE —

PUMP DISCHARGE LINE

- 2. EROSION CONTROL BLANKET SHALL BE INSTALLED VERTICALLY DOWNSLOPE.
- 3. STAKES/STAPLES SHALL BE PLACED NO MORE THAN 3 FT APART VERTICALLY, AND 1 FT APART HORIZONTALLY.
- 4. SLOPE SURFACE SHALL BE FREE OF STICKS, ROCKS, AND OTHER OBSTRUCTIONS.
- 5. BLANKETS SHALL BE ROLLED OUT LOOSELY AND STAKED/STAPLED TO MAINTAIN DIRECT SOIL CONTACT. DO NOT STRETCH THE BLANKETS.



-100% BIODEGRADABLE

COMPOST FILTER TUBE

── COURSE

GROUND SLOPE

FILTER BAG

<u>PLAN</u>

FILTER FABRIC MAT-

SECTION A-A

SEDIMENT TRAP NO SCALE SEDIMENT FREE WATER TO NATURAL WATER

-100% BIODEGRADABLE


COMPOST FILTER TUBE

WOOD STAKE

NOTES:
1. REMOVE FOLLOWING CONSTRUCTION.


TEMPORARY CONSTRUCTION ENTRY PAD

NO SCALE



NOTES:

- 1. TUBES FOR COMPOST FILTERS SHALL BE JUTE MESH OR APPROVED BIODEGRADABLE MATERIAL. ADDITIONAL TUBES SHALL BE USED AT THE DIRECTION OF THE ENGINEER.
- 2. TAMP TUBES IN PLACE TO ENSURE GOOD CONTACT WITH SOIL SURFACE. IT IS NOT NECESSARY TO TRENCH TUBES INTO EXISTING GRADE.
- 3. WHEN STAKING IS NOT POSSIBLE, SUCH AS WHEN TUBES MUST BE PLACED ON PAVEMENT, HEAVY CONCRETE OR CINDER BLOCKS CAN BE USED BEHIND TUBES UP TO 5' APART OR AS REQUIRED TO SECURE TUBES IN PLACE.



PLAN VIEW - JOIN DETAIL

EROSION CONTROL BARRIER COMPOST FILTER TUBE

NOTES:


- 1. PROVIDE 3' MINIMUM OVERLAP AT ENDS OF TUBES TO JOIN IN A CONTINUOUS BARRIER AND MINIMIZE UNIMPEDED FLOW.
- 2. STAKE JOINING TUBES SNUGLY AGAINST EACH OTHER TO PREVENT UNFILTERED FLOW BETWEEN THEM.
- 3. SECURE ENDS OF TUBES WITH STAKES SPACED 18" APART THROUGH TOPS OF TUBES.


GENERAL COMPOST FILTER TUBE NOTES:

- 1. PROVIDE A MINIMUM TUBE DIAMETER OF 12" FOR SLOPES UP TO 50' IN LENGTH WITH A SLOPE RATIO OF 3H:1V OR STEEPER. LONGER SLOPES OF 3H:1V MAY REQUIRE LARGER TUBE DIAMETER OR ADDITIONAL COURSING OF FILTER TUBES TO CREATE A FILTER BERM. REFER TO MANUFACTURER'S RECOMMENDATIONS FOR SITUATIONS WITH LONGER SLOPES OR STEEPER SLOPES.
- 2. INSTALL TUBES ALONG CONTOURS AND PERPENDICULAR TO SHEET OR CONCENTRATED FLOW.
- 3. DO NOT INSTALL IN PERENNIAL, EPHEMERAL OR INTERMITTENT STREAMS.
- 4. CONFIGURE TUBES AROUND EXISTING SITE FEATURES TO MINIMIZE SITE DISTURBANCE AND MAXIMIZE CAPTURE AREA OF STORMWATER RUN-OFF.
- 5. TUBES CAN BE PLACED DIRECTLY ON EXISTING PAVEMENT WHEN NECESSARY.
- 6. PLACING TUBES AGAINST THE UPHILL SIDE OF WELL-ANCHORED, STATIONARY
- FEATURES SUCH AS EXISTING TREES, CAN PROVIDE ADDITIONAL BRACING.

 7. CURVE ENDS UPHILL TO PREVENT DIVERSION OF UNFILTERED RUN-OFF.
- 8. STRAW WATTLES WITH A 100% BIODEGRADABLE MESH MAY BE SUBSTITUTED IN AREAS INACESSIBLE FOR FILTER TUBE INSTALLATION EQUIPMENT.

Tighe&Bond





Salmon Brook Dam Removal Project

Massachusetts
Division of
Fisheries and
Wildlife

Brookfield, Massachusetts

1	9/24	Issued For Bidding
MARK	DATE	DESCRIPTION
PROJECT NO:		M0944-051
DATE:		9/2024
FILE:	C-201 ER	OSION CONTROL DETAILS.dwg

DRAWN BY: CMH/ARG,LPT
DESIGNED/CHECKED BY: DRB/DRH

APPROVED BY:

EROSION, SEDIMENT, AND WATER CONTROL DETAILS

CALE: AS SHOWN

C-201