

**SCITUATE FORESHORE PROTECTION REPAIRS
SCITUATE, MA**

CONTRACT NO. 25-FS-02

ADDENDUM NO. 1

To: Prospective Bidders
From: David Smith/Senior Project Manager, GZA GeoEnvironmental, Inc.
Date: March 28, 2025

Please find the following items to be incorporated into the above referenced Contract, as **Addendum No.1**. Acknowledgement of this Addendum is required when submitting the bid.

1. **CHANGE: The bid due date has been changed to Thursday, April 10, 2025, at 3:00PM.**

2. **QUESTIONS:**

Q1: For the bid items that are reconstruction by the linear foot (02300-4N, 02300-4J), is the intent that all existing rock and sand be excavated to establish a new subgrade and install the core stone and armor stone layers? And the following items for armor stone and core stone by the ton would only be for what is needed after existing stone is used?

A1: **Yes. Existing suitable stone will be used in conjunction with supplemental stone.**

Q2: And for the repair items by the linear foot (02300-1N, 02300-1J, 02300-12J, 02300-15, 02300-18, 02300-19), is the intent to not remove all of the existing (excavate to new subgrade), but rather adjust existing stone and supplement as needed with bid items that follow those by the ton?

A2: **Yes.**

Q3: Are there any time of year restrictions for contractor's use of the gravel parking area by Baileys Causeway?

A3: **Yes, although the Town is open to discuss the reason/needs at the time.**

Q4: Is the intent that all railing will be removed and replaced where new wall cap is proposed? If the railing is not suitable for reuse, how will that cost be handled?

A4: The railing shall be removed and reset, per the drawings. If it is determined by the Town and/or Engineer that the railing cannot be reused, then that would be considered extra work.

Q5: Regarding the spalling detail shown on sheet 6, are there quantities that can be associated with the different depths listed?

A5: No, spall repairs included in the Work are incidental to the concrete seawall crack repair items. Refer to Seawall Spall Repair Notes No. 1, Drawings sheet 6 of 9.

Q6: Spall repair is only proposed in areas of crack repairs?

A6: Yes.

Q7: There are pay items for “Toe Revetment Reconstruction” and for “Toe Revetment Repair”. Please clarify the difference between these, it’s not clear from the drawings

A7: There is no difference. In labeling the Add-Alt1 work, the repair terminology was used.

Q8: Item 02300-11N is for reshaping the upper rip rap slope. The cross sections indicate supplemental stone may be required however there isn’t a corresponding per Ton item for that potential stone. Please clarify.

A8: Stone, whether reuse of existing, or supplemental, is incidental that that item.

Q9: At the Glades/Gannett Access Pad/Ramp Reconstruction is the revetment reconstruction entirely re-using existing stone?

A9: The revetment stone will be reuse of existing suitable stone and supplemental stone to the lines and grades as shown on the drawings.

Q10: Please provide the plan holders list if available.

A10: Current list is located at www.accentblueprints.com.

Q11: I saw a detail for seawall spall repair on sheet 6 but I don’t see where that is called out? Can you clarify?

A11: (see question and response No. 6 above).

Q12: Could you confirm the intent for temporary fence and keeping stairs and beaches open.

A12: Temporary fence is to keep the public away from the work and staging areas. We would like to accommodate the public access to the beach as much as possible, however if it is not safe to do so, then temporary closures using the temporary fencing maybe required.

Q13: Could you share the prebid sign in sheet as well as the plan holders list.

A13: Pre-bid sign in sheet attached. Current plan holder list is located at www.accentblueprints.com.

Q14: Would you consider extending the bid date a week?

A14: (see No. 1). Bid due date extended to April 10, 2025, at 3pm.

ADDENDUM NO. 1 INCLUDES 3 PAGES, PLUS 2 PAGE PRE-BID LIST ATTACHMENT

END OF ADDENDUM NO. 1

Pre-Bid Meeting

Scituate Foreshore Protection Repairs

Site 1 – Glades, Gannett Rds, and 7 Surfside Rd
Site 2 – 91 Surfside Rd
Site 3 – Seaside Rd

March 19, 2025 – 9:00 A.M.

NAME & TITLE <small>(Please Print Clearly)</small>	COMPANY & ADDRESS	EMAIL & PHONE
David Smith Project Manager	GZA GeoEnvironmental, Inc. 144 Elm Street, Amesbury, MA 01913	David.smith@gza.com 781-278-4806
MIKE SALVO Rain for Rent	Rain for Rent	msalvo@rainforrent.com 508 958-1859
Mike Brooks Estimating	A.A. Will Corporation	mbrooks@aawill.com 781-341-4800
Bill Peach	T Ford Company 124 Tenney Street Georgetown, MA	bill@tford.com 978-995-5787
ADAM LUNDSTED	SUMCO ECO CONTRACTING	alundsted@sumcoeco.com 603-732-6830

NAME & TITLE <small>(Please Print Clearly)</small>	COMPANY & ADDRESS	EMAIL & PHONE
Ron Ferrafiuolo Team Lead	SumCo Eco-Contracting 2 CENTENNIAL DR. STE 4D PSABODY, MA 01960	rferr@sumcoeco.com 508-989-0007
Seth McNally Project Manager	J Bates and Son 57 Lawrence St. Clinton, MA 01510	smcnally@jbatesandson.com 978-368-7001